




KA-2100-01 Roe Ave. over I-435

Overland Park, Johnson County

CD 01

N: 38.932957 E: -94.639803 (Approximate)

NE ¼, SW ¼, Section 9, T13S, R25E

10/20/2012

KANSAS DEPARTMENT OF TRANSPORTATION




RTE./CO.	I-435 / Johnson	SOUNDING NO.	CD 01	SHEET 1 of 3
BRIDGE STA.	369+99.28	PROJ. NO.	435-46 KA-2100-01	BRIDGE NONB1.75(415)&SB1.74(418)
SITE NAME	NB & SB Roe over I-435			HOLE STA. 219+35, 49.0' Lt CL
GEOLOGIST	R. Crow, P.G.	SCALE	1 inch = 5.0 feet	DATE August 20, 2012
DRILLER	R. Vervynck	RIG TYPE	CME 55	TOP HOLE ELEV. 873.01
GW ELEV.	862.5	TOTAL DEPTH	51.8	M/B ELEV. 870.01

Bit Type	GEOLOGIC NAME	STRATIGRAPHIC COLUMN	DEPTH	ELEVATION	CLASSIFICATION OF MATERIALS DESCRIPTION AND REMARKS	UNCONFINED COMPRESSION (TSF)	ELASTIC MODULUS (PSF)	N60 COUNT (SPT)	ELEVATION
8" Hollow Augers	Mantle			873.0	Limestone rubble, silty clay, fill material				
	Quivira Shale Mbr.		3.0	870	Limestone	383	1.59E+08		869.41
			3.9	869.1	Shale, gray, limy				
			4.1	868.9	Limestone				
			4.6	868.4	Shale, gray				
NQ2 Diamond	Westerville Limestone Mbr.		7.7	865	Limestone, nearly white, hard, wavy-bedded, slightly pitted, stylolytic seams	915	2.05E+08		863.11
				860					
	Wea Shale Member		13.7	859.3	Shale, very dark gray, occasional vertical fractures	9.6	800000		857.01
				855					
			4			29	2260000		852.21
			5	850		35	2550000		848.51
			6						
			7	845		32	5300000		843.31

BOREHOLE REPORT - KANSAS DOT GDT - 11/28/12 08:21 - Q:\GEOLOGY\BRIDGE\435-46 KA-2100-01\KA-2100-01 ROE OVER I-435.GPJ

KANSAS DEPARTMENT OF TRANSPORTATION

RTE./CO.	I-435 / Johnson	SOUNDING NO.	CD 01	SHEET 2 of 3
BRIDGE STA.	369+99.28	PROJ. NO.	435-46 KA-2100-01	BRIDGE NONB1.75(415)&SB1.74(418)
SITE NAME	NB & SB Roe over I-435			HOLE STA. 219+35, 49.0' Lt CL

Bit Type	GEOLOGIC NAME	STRATIGRAPHIC COLUMN	DEPTH	ELEVATION	CLASSIFICATION OF MATERIALS DESCRIPTION AND REMARKS	UNCONFINED COMPRESSION (TSF)	ELASTIC MODULUS (PSF)	N60 COUNT (SPT)	ELEVATION
NQ2 Diamond	Wea Shale Member		7		Shale, very dark gray, occasional vertical fractures				
			8	840		42	3110000		838.31
			9	835		23	2080000		831.41
			41.8	830	831.2 Shale, gray, laminar, limy, small white shell fossils				
	Bpgk Ls		45.2		827.8 Limestone, gray, hard	745	2.11E+08		826.81
			46.3		826.7 Limestone, very shaly, fossiliferous				
	Fontana Shale Mbr.		47.5	825	825.5 Shale, very dark gray, firm, laminar	102	2.15E+07		823.71
			11						
			51.8		T.D. = 51.8				
				821.21					

