


1 LOCATION OF WATER WELL: Fraction SW 1/4 SE 1/4 SW 1/4 Section Number 6 Township Number T 13 S Range Number R 3 E  
 County Dickinson  
 Distance and direction from nearest town or city street address of well if located within city?

1 West of Detroit and 1/2 North

2 WATER WELL OWNER: Wilfred Witte  
 RR#, St. Address, Box # RR # 1 Board of Agriculture, Division of Water Resources  
 City, State, ZIP Code Abilene, Kansas 67410 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:  
  
 4 DEPTH OF COMPLETED WELL: 118 ft. ELEVATION:  
 Depth(s) Groundwater Encountered 1. 103 ft. 2. ft. 3. ft.  
 WELL'S STATIC WATER LEVEL 101 ft. below land surface measured on mo/day/yr 3 / 22 / 83  
 Pump test data: Well water was ft. after hours pumping gpm  
 Est. Yield 14 gpm: Well water was ft. after hours pumping gpm  
 Bore Hole Diameter 9 in. to 118 ft., and in. to ft.  
 WELL WATER TO BE USED AS:  
 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)  
 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well  
 Was a chemical/bacteriological sample submitted to Department? Yes No \*; If yes, mo/day/yr sample was submitted  
 Water Well Disinfected? Yes \* No

5 TYPE OF BLANK CASING USED:  
 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued \* Clamped  
 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded  
 7 Fiberglass Threaded  
 Blank casing diameter 5 in. to 118 ft., Dia in. to ft., Dia in. to ft.  
 Casing height above land surface 24 in., weight 160 lbs./ft. Wall thickness or gauge No. .214  
 TYPE OF SCREEN OR PERFORATION MATERIAL:  
 1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 10 Asbestos-cement  
 2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify)  
 9 ABS 12 None used (open hole)  
 SCREEN OR PERFORATION OPENINGS ARE:  
 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)  
 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes  
 7 Torch cut 10 Other (specify)  
 SCREEN-PERFORATED INTERVALS: From 98 ft. to 118 ft., From ft. to ft.  
 From ft. to ft., From ft. to ft.  
 GRAVEL PACK INTERVALS: From 10 ft. to 118 ft., From ft. to ft.  
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other  
 Grout Intervals: From 0 ft. to 10 ft., From ft. to ft., From ft. to ft.  
 What is the nearest source of possible contamination:  
 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well  
 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well  
 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)  
 13 Insecticide storage  
 Direction from well? SOUTHWEST How many feet? 600

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	17	Y ELLow CLAY & SHALE	100	101	YELLOW GRAY SHALE
17	27	LIMESTONE	101	102	SOFT LIMESTONE
27	29	YELLOW CLAY	102	103	RED & YELLOW SHALE
29	34	RED CLAY	103	110	LITE YELLOW SHALE
34	41	YELLOW CLAY	110	115	LITE HARD LIMESTONE
41	44	RED CLAY	115	118	GRAY CLAY & GYPSUM
44	48	LITE COLOR SHALE			
48	61	YELLOW CLAY			
61	68	LIMESTONE			
68	74	BLUE CLAY			
74	78	BLUE SHALE			
78	81	LIMESTONE			
81	84	YELLOW SHALE			
84	98	RED CLAY & SHALE			
98	100	SOFT RED CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 3 / 22 / 83 and this record is true to the best of my knowledge and belief. Kansas  
 Water Well Contractor's License No. 397 This Water Well Record was completed on (mo/day/year) 4 / 28 / 83  
 under the business name of CENTRAL KANSAS DRILLING by (signature) Harold D. Martin  
 INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.

OFFICE USE ONLY  
 T  
 13  
 R  
 3  
 DW  
 SEC.  
 SW 1/4  
 SE 1/4  
 SW 1/4