

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: WABAUNSEE	NE 1/4 NE 1/4 NW 1/4	6	T 14 S	R 13 E/W

Distance and direction from nearest town or city street address of well if located within city?

4 1/4 east, 3/4 north of Eskridge2 WATER WELL OWNER: **Wittmer & Associates**RR#, St. Address, Box #: **1136 S.W. Wanamaker**

Board of Agriculture, Division of Water Resources

City, State, ZIP Code: **Topeka, Kansas**

Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL: **160'** ft. ELEVATION:Depth(s) Groundwater Encountered **1. 83'** ft. 2. ft. 3. ft.WELL'S STATIC WATER LEVEL **70'** ft. below land surface measured on mo/day/yr **5-19-94**

Pump test data: Well water was ft. after hours pumping gpm

Est. Yield **1 1/2** gpm: Well water was ft. after hours pumping gpmBore Hole Diameter **8"** in. to ft. and in. to ft.

WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well

1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)

2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well

Was a chemical/bacteriological sample submitted to Department? Yes No **X**; If yes, mo/day/yr sample was submittedWater Well Disinfected? Yes **X** No

5 TYPE OF BLANK CASING USED:

1 Steel 3 RMP (SR)

5 Wrought iron

8 Concrete tile

CASING JOINTS: Glued **X** Clamped

2 PVC 4 ABS

6 Asbestos-Cement

9 Other (specify below)

Welded

Blank casing diameter **5"** in. to **0-70** ft. Dia **5"** in. to **106-159** ft. DiaCasing height above land surface **24"** in. weight **2.82** lbs./ft. Wall thickness or gauge No. **258**

TYPE OF SCREEN OR PERFORATION MATERIAL:

1 Steel 3 Stainless steel

5 Fiberglass

7 PVC

10 Asbestos-cement

2 Brass 4 Galvanized steel

6 Concrete tile

8 RMP (SR)

11 Other (specify)

12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:

1 Continuous slot 3 Mill slot

5 Gauzed wrapped

8 Saw cut

11 None (open hole)

2 Louvered shutter 4 Key punched

6 Wire wrapped

9 Drilled holes

7 Torch cut

10 Other (specify)

SCREEN-PERFORATED INTERVALS: From **70** ft. to **106** ft. From ft. to ft.From **159** ft. to **160** ft. From ft. to ft.GRAVEL PACK INTERVALS: From **24** ft. to **160** ft. From ft. to ft.

From ft. to ft. From ft. to ft.

6 GROUT MATERIAL:

1 Neat cement

2 Cement grout

3 Bentonite

4 Other

Grout Intervals: From **4** ft. to **24** ft. From ft. to ft.

What is the nearest source of possible contamination:

1 Septic tank

4 Lateral lines

7 Pit privy

10 Livestock pens

14 Abandoned water well

2 Sewer lines

5 Cess pool

8 Sewage lagoon

11 Fuel storage

15 Oil well/Gas well

3 Watertight sewer lines 6 Seepage pit

9 Feedyard

12 Fertilizer storage

16 Other (specify below)

13 Insecticide storage

Direction from well?

northHow many feet? **300'**

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	7	Clay-Brown	115	118	Limestone-grey
7	11	Shale-Grey	118	138	Shale-Red
11	15	Limestone-grey	138	141	Limestone-Grey
15	44	Shale-Grey	141	149	Shale-Grey
44	45	Limestone-Grey	149	152	Limestone-Grey
45	54	Shale-Grey	152	160	Shale-Grey
54	57	Limestone-grey			
57	64	Shale-Grey			
64	65	Limestone-grey			
65	75	Shale-Grey			
75	83	Sandstone-grey			
83	90	Limestone-Grey			
90	106	Shale-Grey			
106	110	Limestone-Grey			
110	115	Shale-Grey			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) **5-19-94** and this record is true to the best of my knowledge and belief. KansasWater Well Contractor's License No. **182** This Water Well Record was completed on (mo/day/yr) **6-1-94**under the business name of **STRADER DRILLING CO., INC.**by (signature) *Dale Strader*

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.