

CORRECTION(S) TO WATER WELL RECORD (WWC-5)

(to rectify lacking or incorrect information)

County: Johnson

Location listed as:

Location ~~changed to:~~

Section-Township-Range: _____

24-14S-22EFraction ($\frac{1}{4}$ $\frac{1}{4}$ $\frac{1}{4}$): _____SW SE SW

Other changes: Initial statements: _____

County listed: Shawnee

Changed to: _____

Johnson Co.

Comments: _____

verification method: _____

Well address, city map on internet, Gardner1:24,000 topo. map.initials: E.P.date: 10/5/2005

submitted by: Kansas Geological Survey, Data Resources Library, 1930 Constant Ave., Lawrence, KS 66047-3726

to: Kansas Dept of Health & Environment, Bureau of Water, 1000 SW Jackson, Suite 420, Topeka, KS 66612-1367.

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.

Date Drilled: 7-12-04 Screen Diam: 2" Drilling Co: Max's Enterprises
 Total depth: 15.0' Length: 10.0' Method: Hollow stem auger
 Hole diameter: 8.0" Slot Size: .010 Driller: Doug Hunziker
 Elev. G.L.: TOC Casing Dia: 2" Geologist: Scott B. McDaniel
 Water elev.: Initial 8.50' Static 8.50' Length: 5.0' Sampling Method(s): Continuous core
 Type: EMT Analysis Equip: GasTech PID

Sample depth	Headspace (ppm)1	Well schematic	Depth (feet)	Lithologic Description ²	Observations/Remarks ³
			1	0-0.2' Asphalt cap	Mobil 857 Drill Rig
			2	0.2-3.8' Brown (light to reddish brown, stiff, high plastic, w/ silty gravel clay (CH))	Estimated Moisture Contents: @ 5' = 20% @ 10' = 25%+
			3	3.8'-15' Brown to gray, dense fine-coarse grained silty clayey sand (SM)	
			4	with hydrocarbon odor & gray staining, to total depth	Estimated initial H ₂ O level @ 8.50'
5'	480		5	occasional rainbow sheen	
			6		
			7	with laminations throughout	
			8		
9'	360		9		
			10		
			11		
			12		
			13		
			14		
15'	460		15	Total depth = 15.0'	
			16		
			17		
			18	* Reserve sample for laboratory	

Well logged by _____, Geologist
 1) Headspace by PID or detector tube measurement. 2) Lithologic description includes color, sorting, size, texture, and size and shape of grains etc. 3) Observations/Remarks include fracturing, solution cavities, odor, staining, organic content, moisture content, etc.
 Tank Management Services, Inc., Topeka, Kansas (785) 233-1414