


1 LOCATION OF WATER WELL: County: Johnson		Fraction NE 1/4 NE 1/4 NE 1/4	Section Number 12	Township Number T 14 S	Range Number R 23 (EW)
Distance and direction from nearest town or city street address of well if located within city? 1805 S. Ridgeview, Olathe, KS.					
2 WATER WELL OWNER: Criswell Petroleum Products RR#, St. Address, Box #: 916 S. 9th City, State, ZIP Code: St. Joseph, MO. 64503 Board of Agriculture, Division of Water Resources Application Number:					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL. 22 1/2' ft. ELEVATION: Depth(s) Groundwater Encountered 1 17' ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL 8'9 1/2" ft. below land surface measured on mo/day/yr 3-18-95 Pump test data: Well water was ft. after hours pumping gpm Est. Yield gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter. 8'9 1/2" in. to 22 1/2' ft., and in. to ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only (10) Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes. No. X If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes No (X)			
5 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped (2) PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded Blank casing diameter 2.375 in. to 12 1/2' ft., Dia in. to ft., Dia in. to SDR 13 ft. Casing height above land surface Flush Ground , weight lbs./ft. Wall thickness or gauge No. SCH 40 TYPE OF SCREEN OR PERFORATION MATERIAL: (7) PVC 10 Asbestos-cement 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot (3) Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes SCREEN-PERFORATED INTERVALS: From 22 1/2' ft. to 12 1/2' ft., From ft. to ft. GRAVEL PACK INTERVALS: From 22 1/2' ft. to 10' ft., From ft. to ft. From ft. to ft., From ft. to ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Grout Intervals: From 10' ft. to 3' ft., From 3' ft. to 0' ft., From ft. to ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy (11) Fuel storage 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage 16 Other (specify below) Direction from well? West How many feet? 70'					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	.75	asphalt w/ ls rx. gravel base.			
.75	18	Gray-brownish gray mottled clay, iron oxides, plastic, tight, ropey clay, moist, no odor, blk root casts.			
18	21	Yellow-brn gray clay, iron oxides, mottled, moist to wet, caliche, no odor.			
21	22.50	Dk yellow brn shale, dry, no odor.			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed , (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 3-8-95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 539 This Water Well Record was completed on (mo/day/yr) 3-26-95 under the business name of JB Environmental Drilling by (signature) James Beber					