

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

1 LOCATION OF WATER WELL: County: <u>Waubesa</u> Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ <u>700 Main Street</u> <u>Alta Vista, KS 66834</u>		Fraction <u>NW 1/4 NE 1/4 SW 1/4 NE 1/4</u>		Section Number <u>2</u>		Township No. <u>T 12 S</u>		Range Number <u>R 8 E</u> ☒ <u>W</u>																																											
2 WATER WELL OWNER: RR#, Street Address, Box #: City, State, ZIP Code		<u>KDHE - BET</u> <u>1000 SW Jackson</u> <u>Topeka, KS 66612</u>		Global Positioning System (GPS) information: Latitude: <u>N38.865329</u> (in decimal degrees) Longitude: <u>W96.489464</u> (in decimal degrees) Elevation: _____ Datum: ☐ WGS 84, ☒ NAD 83, ☐ NAD 27 Collection Method: ☒ GPS unit (Make/Model: <u>Garmin Nuvi 760</u>) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m																																															
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N <table border="1" style="width: 100%; height: 100px; border-collapse: collapse;"> <tr> <td style="width: 50%; text-align: center;">NW</td> <td style="width: 50%; text-align: center;">NE</td> </tr> <tr> <td style="width: 50%; text-align: center;">SW</td> <td style="width: 50%; text-align: center;">SE</td> </tr> </table> S ----- 1 mile -----		NW	NE	SW	SE	4 DEPTH OF COMPLETED WELL <u>18</u> ft. Depth(s) Groundwater Encountered (1) <u>Dry</u> ft. (2) <u>N/A</u> ft. (3) <u>N/A</u> ft. WELL'S STATIC WATER LEVEL <u>Dry</u> ft. below land surface measured on mo/day/yr. <u>2/21/2012</u> Pump test data: Well water was <u>N/A</u> ft. after <u>N/A</u> hours pumping <u>N/A</u> gpm EST. YIELD <u>N/A</u> gpm. Well water was <u>N/A</u> ft. after <u>N/A</u> hours pumping <u>N/A</u> gpm Bore Hole Diameter <u>8.25</u> in. to <u>18</u> ft. and <u>N/A</u> in. to <u>N/A</u> ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☐ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☒ Monitoring well <u>MW-4</u> Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted <u>N/A</u> Water well disinfected? ☐ Yes ☒ No																																													
NW	NE																																																		
SW	SE																																																		
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other _____ CASING JOINTS: ☐ Glued ☐ Clamped ☐ Welded ☒ Threaded Casing diameter <u>2</u> in. to <u>8</u> ft., Diameter <u>N/A</u> in. to <u>N/A</u> ft., Diameter <u>N/A</u> in. to <u>N/A</u> ft. Casing height above land surface <u>0</u> in., Weight _____ lbs./ft., Wall thickness or gauge No. <u>Sch 40</u> TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) _____ ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☒ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☐ Saw cut ☐ Other (specify) _____ SCREEN-PERFORATED INTERVALS: From <u>8</u> ft. to <u>18</u> ft. From <u>N/A</u> ft. to <u>N/A</u> ft. From <u>N/A</u> ft. to <u>N/A</u> ft. GRAVEL PACK INTERVALS: From <u>6</u> ft. to <u>18</u> ft. From <u>N/A</u> ft. to <u>N/A</u> ft. From <u>N/A</u> ft. to <u>N/A</u> ft.																																																			
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☒ Other <u>Concrete from 0-2'</u> Grout Intervals: From <u>2</u> ft. to <u>6</u> ft. From <u>N/A</u> ft. to <u>N/A</u> ft. From <u>N/A</u> ft. to <u>N/A</u> ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☐ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☒ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well Direction from well _____ Distance from well <u><100ft</u>																																																			
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>1</td> <td>concrete</td> <td>12</td> <td>14</td> <td>ML: yellow sandy SLT, damp, non-plastic, medium</td> </tr> <tr> <td>1</td> <td>3</td> <td>CH: dark grey CLAY, damp to moist, plastic, soft</td> <td>14</td> <td>18</td> <td>weathered sandy LIMESTONE</td> </tr> <tr> <td>3</td> <td>5.5</td> <td>CH: reddish brown CLAY, moist, plastic, soft</td> <td></td> <td></td> <td></td> </tr> <tr> <td>5.5</td> <td>8</td> <td>CL: light brown CLAY, moist, TR plastic, soft</td> <td></td> <td></td> <td></td> </tr> <tr> <td>8</td> <td>11</td> <td>CL: light brown, silty CLAY, moist, non-plastic, soft w/ LS gravels</td> <td></td> <td></td> <td></td> </tr> <tr> <td>11</td> <td>12</td> <td>CL: red-gy CLAY, damp, non-plastic</td> <td></td> <td></td> <td></td> </tr> </tbody> </table>										FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	1	concrete	12	14	ML: yellow sandy SLT, damp, non-plastic, medium	1	3	CH: dark grey CLAY, damp to moist, plastic, soft	14	18	weathered sandy LIMESTONE	3	5.5	CH: reddish brown CLAY, moist, plastic, soft				5.5	8	CL: light brown CLAY, moist, TR plastic, soft				8	11	CL: light brown, silty CLAY, moist, non-plastic, soft w/ LS gravels				11	12	CL: red-gy CLAY, damp, non-plastic			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																														
0	1	concrete	12	14	ML: yellow sandy SLT, damp, non-plastic, medium																																														
1	3	CH: dark grey CLAY, damp to moist, plastic, soft	14	18	weathered sandy LIMESTONE																																														
3	5.5	CH: reddish brown CLAY, moist, plastic, soft																																																	
5.5	8	CL: light brown CLAY, moist, TR plastic, soft																																																	
8	11	CL: light brown, silty CLAY, moist, non-plastic, soft w/ LS gravels																																																	
11	12	CL: red-gy CLAY, damp, non-plastic																																																	
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) <u>2/21/2012</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>759</u> This Water Well Record was completed on (mo/day/year) <u>3/1/2012</u> under the business name of <u>RAZEK Environmental LLC</u> by (signature) <u>[Signature]</u>																																																			
INSTRUCTIONS: Use typewriter or ball point pen. <u>PLEASE PRESS FIRMLY</u> and <u>PRINT</u> clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367 Telephone 785-296-5524. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html																																																			