

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

1 LOCATION OF WATER WELL: County: Waubunsee Street/Rural Address of Well Location: if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ 700 Main Street Alta Vista, KS 66834		Fraction NW 1/4 NE 1/4 SW 1/4 NE 1/4		Section Number 2		Township No. T 14 S		Range Number R 8 ☒ E ☐ W																															
2 WATER WELL OWNER: RR#, Street Address, Box #: KDHE-BER City, State, ZIP Code: 1000 SW Jackson Topeka, KS 66612				Global Positioning System (GPS) information: Latitude: N38.865329 (in decimal degrees) Longitude: W96.489464 (in decimal degrees) Elevation: _____ Datum: ☐ WGS 84, ☒ NAD 83, ☐ NAD 27 Collection Method: ☒ GPS unit (Make/Model: Garmin Nuvi 760) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m																																			
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N S 1 mile		4 DEPTH OF COMPLETED WELL 17.5 ft. Depth(s) Groundwater Encountered (1) Dry ft. (2) N/A ft. (3) N/A ft. WELL'S STATIC WATER LEVEL: Dry ft. below land surface measured on mo/day/yr. 2/20/2012 Pump test data: Well water was N/A ft. after N/A hours pumping N/A gpm EST. YIELD: N/A gpm. Well water was N/A ft. after N/A hours pumping N/A gpm Bore Hole Diameter 8.25 in. to 17.5 ft., and N/A in. to N/A ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☐ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☒ Monitoring well MW-5 Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted N/A Water well disinfected? ☐ Yes ☒ No																																					
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other _____ CASING JOINTS: ☐ Glued ☐ Clamped ☐ Welded ☒ Threaded Casing diameter 2 in. to 7.5 ft., Diameter N/A in. to N/A ft., Diameter N/A in. to N/A ft. Casing height above land surface 0 in., Weight _____ lbs./ft., Wall thickness or gauge No. Sch 40 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) _____ ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☒ Mill slot ☐ Gauge wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☐ Saw cut ☐ Other (specify) _____ SCREEN-PERFORATED INTERVALS: From 7.5 ft. to 17.5 ft., From N/A ft. to N/A ft., From N/A ft. to N/A ft. GRAVEL PACK INTERVALS: From 5.5 ft. to 17.5 ft., From N/A ft. to N/A ft., From N/A ft. to N/A ft.																																							
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☒ Other Concrete from 0-2' Grout Intervals: From 2 ft. to 5.5 ft., From N/A ft. to N/A ft., From N/A ft. to N/A ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☐ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☒ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Sepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well Direction from well _____ Distance from well <100ft																																							
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>3</td> <td>CH: dark brown CLAY, moist, high plastic, soft</td> <td></td> <td></td> <td></td> </tr> <tr> <td>3</td> <td>8.5</td> <td>CH: red-brown CLAY, damp, plastic, very stiff</td> <td></td> <td></td> <td></td> </tr> <tr> <td>8.5</td> <td>15</td> <td>CL: light brown, silty CLAY, damp, non-plastic, stiff, w/ intermittent limestone gravels</td> <td></td> <td></td> <td></td> </tr> <tr> <td>15</td> <td>17.5</td> <td>weathered LIMESTONE w/ sand</td> <td></td> <td></td> <td></td> </tr> </tbody> </table>										FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	3	CH: dark brown CLAY, moist, high plastic, soft				3	8.5	CH: red-brown CLAY, damp, plastic, very stiff				8.5	15	CL: light brown, silty CLAY, damp, non-plastic, stiff, w/ intermittent limestone gravels				15	17.5	weathered LIMESTONE w/ sand			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																		
0	3	CH: dark brown CLAY, moist, high plastic, soft																																					
3	8.5	CH: red-brown CLAY, damp, plastic, very stiff																																					
8.5	15	CL: light brown, silty CLAY, damp, non-plastic, stiff, w/ intermittent limestone gravels																																					
15	17.5	weathered LIMESTONE w/ sand																																					
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 2/20/2012 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 759 This Water Well Record was completed on (mo/day/year) 3/4/2012 under the business name of RAZEK Environmental LLC by (signature) <i>[Signature]</i>																																							
INSTRUCTIONS: Use ballpoint pen or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5524. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																							