

1	LOCATION OF WATER WELL: County: Franklin	Fraction SE ¼ SE ¼ SW ¼	Section Number 34	Township Number T 16 S	Range Number R 18E E/W
---	--	-----------------------------------	-----------------------------	----------------------------------	----------------------------------

Distance and direction from nearest town or city street address of well if located within city?
2 miles East of Pomona Franklin co Permit # 07-WW-FR-022

2 WATER WELL OWNER: **Sharon Sparks** site: **1175 Hiway 68, Pomona, Ks 66076**
 RR#, St. Address, Box # : **9830 Killcreek** Board of Agriculture, Division of Water Resources
 City, State, ZIP Code : **Desoto, Ks. 66018** Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

N			
-NW-		-NE-	
W			E
-SW-		-SE-	
		X	
		S	

4 DEPTH OF COMPLETED WELL**15.1**..... ft. ELEVATION:

Depth(s) Groundwater Encountered 1 ft. 2 ft. 3 ft.
 WELL'S STATIC WATER LEVEL**4.1**..... ft. below land surface measured on mo/day/yr **1-3-08**

Pump test data: Well water was ft. after hours pumping gpm
 Est. Yield**6.0**..... gpm: Well water was ft. after hours pumping gpm

WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well
 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)
 2 Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well

Was a chemical/bacteriological sample submitted to Department? Yes No **X**.....; If yes, mo/day/yr sample was submitted
 Water Well Disinfected? Yes **X** No

5 TYPE OF BLANK CASING USED: 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued **X** Clamped
 1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) Welded
 2 PVC 4 ABS 7 Fiberglass Threaded

Blank casing diameter**5**..... in. to ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface**2.4**..... in., weight**2.82**..... lbs./ft. Wall thickness or guage No. **.258**

TYPE OF SCREEN OR PERFORATION MATERIAL: 7 PVC 10 Asbestos-Cement
 1 Steel 3 Stainless Steel 5 Fiberglass 8 RMP (SR) 11 Other (Specify)
 2 Brass 4 Galvanized Steel 6 Concrete tile 9 ABS 12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE: 5 Guazed wrapped 8 Saw cut 11 None (open hole)
 1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes
 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)

SCREEN-PERFORATED INTERVALS: From **101** ft. to **141** ft., From ft. to ft.
 From ft. to ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From **35** ft. to **151** ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other

Grout Intervals: From **2** ft. to **35** ft., From ft. to ft., From ft. to ft.

What is the nearest source of possible contamination:
 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well
 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well
 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)
 13 Insecticide storage

Direction from well? ~~XXXX~~ **Southwest** How many feet? **105'**

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	top soil			
3	14	clay brown/with gravel			
14	17	shale yellow			
17	23	sandstone yellow			
23	27	shale shale yellow brown			
27	36	sandstone brown shaley			
36	59	sandstone grey shaley			
59	76	shale grey			
76	144	sandstone grey			
144	151	sandstone grey hard			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) **1-3-08** and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's Licence No **182** This Water Well Record was completed on (mo/day/yr) **1-19-08** under the business name of **Strader Drilling Co., Inc.** by (signature) *Jim Strader*