

Plotted
Hunt

17-16-21E
17
Form. PO 214 Sheet 1 7-30-20M

LOG OF WELL

SHEET 1

OWNER The Texas Company DIVISION Okla-Kans-Ky. DATE MADE 1/27/40.
 DISTRICT North Kansas LEASE W. H. Shelton WELL NO. Water Well #2
 STATE Kansas COUNTY OR PARISH Franklin TWP. 16 S RANGE 21 E SEC. 17
 LOCATION OF WELL App. 100' from North and 1200' from East lines in the S2 S24

COMMENCED RIGGING UP 12/19/39. COMMENCED DRILLING 12/20/39. COMPLETED DRILLING 12/27/39.
 DRILLER Lloyd Grain NIGHT DRILLER none CONTRACTOR Company Rig
 CABLE FROM 0 TO 150' ROTARY FROM none TO _____ COMPANY RIG No. _____
 TOTAL DEPTH 150' MEASURED BY H. L. Van Deventer ELEVATION _____

CASING RECORD

SIZE	WEIGHT	PUT IN WELL		PULLED OUT		LOST IN WELL		SHOES		PACKERS		
		FEET	INS.	FEET	INS.	FEET	INS.	LENGTH	MAKE	KIND	LENGTH	SET A
<u>8-1/4"</u>	<u>24</u>	<u>13'</u>	<u>9"</u>	<u>13'</u>	<u>9"</u>							

CASING CEMENTED? _____ IF SO, HOW MANY SACKS OF CEMENT USED? _____
 LINER: STATE SIZE AND WEIGHT _____ WHERE SET _____ FT. AND INS. BLANK _____ FT. AND INS. PERFORATED _____
 HOW PUT TOGETHER _____ COUPLING _____ FLUSH-JOINT _____ INSERTED _____
 REMARKS: _____

EQUIPMENT RECORD

TUBING				SUCKER RODS			PUMPING OUTFIT
SIZE	WEIGHT	FEET	INS.	FEET	INS.	SIZE AND KIND	DESCRIPTION, KIND, SIZE, ETC.

FLOWING, PUMPING, GASSER OR DRY Dry PRODUCTION FIRST 24 HOURS _____ PRODUCTION SETTLED _____
 IF GAS WELL, OPEN FLOW CAPACITY _____ SHUT IN PRESSURE _____ ROCK PRESSURE _____
 KIND OF SHOT Dynamite SIZE OF SHOT, QUARTS _____
 NUMBER OF SHELLS _____ SIZE OF SHELLS _____ INCHES, DIAMETER _____
 LENGTH OF SHELLS _____ FEET _____ INCHES _____ TOP OF SHOT _____
 BOTTOM OF SHOT _____ ANCHOR _____ WELL BRIDGED TO _____
 TOTAL DEPTH OF WELL _____ NUMBER OF SHOT _____ PRODUCTION BEFORE SHOT _____ BBLs. PER DAY _____
 PRODUCTION AFTER SHOT _____ BBLs. PER DAY. SHOT FURNISHED BY _____
 NAME OF SHOOTER H. L. Van Deventer SHOT INSPECTED 12/27/39 BY H. L. Van Deventer
 (COMPANY EMPLOYEE)
 COMMENCED DRILLING DEEPER _____ COMPLETED _____ DRILLING DEEPER _____
 TOTAL DEPTH _____ PRODUCTION FIRST 24 HOURS _____ PRODUCTION SETTLED _____

REMARKS: Bridged hole at 30' - Shot with 12 sticks of dynamite. C.O. to 150', bottom of hole. Dry hole---plugged and abandoned 12/27/39.

NOTE: IF WELL WAS DRY, STATE UNDER REMARKS, WHEN, HOW, AND BY WHOM PLUGGED.
 STATE UNDER REMARKS ANYTHING OF INTEREST NOT COVERED IN LOG.
 IF THE SPACE PROVIDED FOR REMARKS IS NOT SUFFICIENT WRITE ON BOTTOM OF LAST SHEET OF LOG.

LOG OF WELL

SHEET NO. 2

17-16-21 E

District **NORTH KANSAS** Owner **THE TEXAS COMPANY** Farm **W. E. SWILSON** Well No.

FORMATION	BOTTOM	AMOUNT	COLOR	HARD or SOFT	DEPTH CORES TAKEN	REMARKS
Soil	1	1	Black	Soft		
Clay	8	7	Brown	"		
Sandy Linn	18	2	Yellow	Med.		
Sandy Linn	23	13	Brown	Hard		
Shale	30	7	Dark	Soft		
Linn	40	10	Gray	Hard		
Shale	50	6	Dark	Med.		
Linn	51	5	Gray	Hard		
Linn	56	5	Gray	Hard		
Shale	61	3	Gray	Soft		
Linn	64	3	Gray	Hard		
Shale	78	16	Gray	Soft		
Shale	95	17	Gray	Soft		
Linn	115	20	Gray	Med.		
Sandy Shale	125	10	Gray	Soft		
Shale	150	25	Dark	Soft		