

24-16-21E

SUTCLIFFE PIPE & SUPPLY ORIGINAL

Well Record

PHONE HE 1-10 CHANUTE
15. TERN. ST. WICHITA

16. CRANT CHANUTE KANSAS
5708 N. BROADWAY, WICHITA KANSAS

COMPLETE LINE OF NEW & USED PIPE • BELTING • STORAGE TANKS • WIRE LINES

Well No. Farm Phillips | Producer, Roger F. Williams

Location | Sec. 24 Twp. 16 S Rg. 21 E

Elevation | State Kansas County Miami

Kind (Oil, Gas, Water, Dry Hole) Water Supply | Contractor Sutcliffe Pipe & Supply

Producing formation | Top Bottom

Shot with qts. from to

Packet set at Kind Size

Inner from to Perforated from to

LOG

Thickness!	Strata	Depth	Thickness	Strata	Depth
2	Soil	2	3	Lime	635
10	Clay	12	10	Shale	645
2	Lime	14	3	Lime	648
3	Shale (Little water)	17	2	Shale	662
6	Lime	23	4	Lime	664
4	Shale	27	7	Shale	668
8	Lime	45	25	Sand-show of oil	675
3	Shale	48	65	Sandy Shale	700
2	Lime	55	2	Shale	765
5	Shale	90	1	Lime	767
7	Lime	107	16	B. Shale	771
8	Shale	195	16	L. Shale	787
0	Lime	215	5	Red Bed	792
5	L. Shale	250	133	Shale	925
5	Lime	255	25	Shale Sandy	950
5	L. Shale	270	35	Sand-water	985
3	Lime	273	9	D. Sandy Shale	994
2	Sandy Shale	285	28	Sand	1022
3	Lime	293	20	Slate	1042
2	Shale	315	73	Lime	1115
2	Lime	390	10	Sandy Lime	1125
2	Shale	550	5	water	1125
2	Lime	557		Lime - dead oil	1130
2	Shale	585			
2	Lime	591			
2	Shale	616			
2	Lime - show oil	621			
2	Slate water	626			
2	Lime	630			
2	Shale	642			

Total Depth 1130'

Open Hole

Casing 8" at 661'

Casing at

Casing at

Cement 90 sacks cement

Tubing

Rods

Additional Information

3 B.W.P.H. @ 215

6 B.W.P.H. @ 374

SLM 616

(Corrected measurement from 925 to

 SLM 897)

Gas at 906

SLM 1045

Running 1052' of 7" and pulling 655' of

 8" and cementing 7"

Testing water fillup - filled up 300' in

 one hour.

Water fillup 300' in one hour.