

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well: County Morris		Fraction NW 1/4 NE 1/4 NE 1/4		Section number 30		Township number T 16 S R 7 E/W		Range number 7			
2. Distance and direction from nearest town or city: 1/2 mile west of Wilsey				3. Owner of well: John Adams							
Street address of well location if in city:				R.R. or street:							
				City, state, zip code: Wilsey, Kansas							
4. Locate with "X" in section below:				Sketch map: Rail Road				6. Bore hole dia. 6.5 in. Completion date 5-28-76		Well depth 121 ft.	
								7. <input checked="" type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug		<input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
5. Type and color of material				From		To		8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry		9. Casing: Material PLS Height Above or below	
Topsoil - BK				0		3		<input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock		Threaded <input type="checkbox"/> Welded glu Surface 18 in.	
Clay - Brn				3		6		<input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		RMP <input checked="" type="checkbox"/> PVC Weight _____ lbs./ft.	
Red Rock				6		10		Dia. 5 in. to 42 ft. depth Wall Thickness: inches or		Dia. _____ in. to _____ ft. depth gage No. 200	
Lime - wht				10		13		10. Screens: Manufacturer's name Sunflower		Type RMP Dia. 5"	
Shale - Yel				13		19		Slot/gauze YB Length 79		Set between 42 ft. and 112 ft.	
Lime - wht				19		21		_____ ft. and _____ ft.		Gravel pack? NO Size range of material _____	
Shale - Yellow				21		24		11. Static water level: _____ mo./day/yr.		42 ft. below land surface Date 5-28-76	
Lime - Yellow				24		27		12. Pumping level below land surfaces:		_____ ft. after _____ hrs. pumping _____ g.p.m.	
Dry Creeks - best Water				27		28		_____ ft. after _____ hrs. pumping _____ g.p.m.		Estimated maximum yield _____ g.p.m.	
Lime - Yell				28		34		13. Water sample submitted: _____ mo./day/yr.		Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date _____	
Shale - Yel				34		36		14. Well head completion:		_____ Pitless adapter 18 inches above grade	
Lime - Broken - wht - Water Show				36		42		15. Well grouted? YES		With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete	
Lime - Hd wht				42		54		Depth: From 3 1/2 ft. to 14 ft.		16. Nearest source of possible contamination: Railroad right of way	
Shale - Blu				54		60		ft. 600ft Direction N Type _____		Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
Lime - Gray				60		63		17. Pump: <input checked="" type="checkbox"/> Not installed		Manufacturer's name _____	
Shale - Blu				63		72		Model number _____ HP _____ Volts _____		Length of drop pipe _____ ft. capacity _____ g.p.m.	
Lime - Gray				72		80		Type:		<input type="checkbox"/> Submersible <input type="checkbox"/> Turbine	
Lime - Gray - Abrasive				80		85		<input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating		<input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
Lime - Broken - wht				85		86		20. Water well contractor's certification:		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.	
Lime - Gray - very Abrasive				86		105		Business name Zinn Water Well Drilling 218		License No. _____	
Shale - Gray				105		109		Address Last Springs, Kan		Date 6-4-76	
Red Rock				109		117		Signed Joseph A. Zinn		Authorized representative	
Lime - Gray - Continues				117		121					
(Use a second sheet if needed)											
18. Elevation:		19. Remarks: Concrete slab to be installed by customer of J. Williams for J. Adams				20. Water well contractor's certification:					
Topography:						This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.					
<input type="checkbox"/> Hill						Business name Zinn Water Well Drilling 218					
<input type="checkbox"/> Slope						License No. _____					
<input checked="" type="checkbox"/> Upland						Address Last Springs, Kan					
<input type="checkbox"/> Valley						Date 6-4-76					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5