

Log of well drilled by H.R. Swank in SW NE sec. 8, T. 17 S., R 20 E.

Franklin County. (1952)

Well No. 1 (dry hole)

Soil	5	
Clay and Gravel	13.5(dry)	
Yellow lime	4	
Blue shale	6	
White lime	14	
Black shale	8	
White lime	12	
Blue shale	10	
White lime	12	
Gray shale	7	
White lime	2	
Blue shale	1	
White lime	12	← Little water
Black Shale	16	← Little water
TD	122.5	
(not used)		

Well No. 2

Soil	3	
Clay(no gravel)	9 (dry)	
Yellow lime	5	
White lime	15	
Black shale	9	
Blue lime	2	
White lime	11	
Sandy blue shale	5	
Blue clay shale	8	
Blue lime	5	
White lime	18	
Black shale	14	} water on top of sd.
White sand	18	
Sandy shale	25	
Blue shale	8	
White sand	7	
Blue shale	1	

TD 161 feet

5 or 6 Bbls water/ day