

WATER WELL RECORD #1

DRILLERS LOG OF WELL

FROM (FT.)	TO (FT.)	KIND OF MATERIAL, COLOR, ETC. (NOTE WATER ZONES, AMOUNT, QUALITY)
0	2	top soil
2	17	limestone, hard, grayish-white
17	21	dark gray shale
21	24	limestone, hard, dark
24	69	limestone, soft grayish- white & shale; mostly limestone
69	71	shale
71	75	shale & slate, show of coal
75	86	shale
86	90	limestone
90	95	shale
95	96	Sandy limestone
96	106	Sandy shale
106	115	Sandy limestone
115	138	Sandy shale
138	148	Sand & shale, broken, hard
148	153	Sandstone, water
		Reduced bit to 6 1/2"
153	183	Sandstone, clean, fine, white
183	192	Shale

Well Owner City of Williamsburg, Kans.

Address Williamsburg, Kans.

Drilling Contractor Jungmann Bros.

Date Drilled Aug 26th to Sept 4, 1957

Method of Drilling Cable tool

Casing: None

(New, Used—Steel, Galv.—Gage or Weight)

Casing Schedule:

(Amount, Size, Setting)

Screen Data (if any): None

ON COMPLETED WELL

Measured depth to water (Static Level) is 127 ft.

below land surface

(Land Surface, Top of Casing, Etc.)

TESTED YIELD: 10 gallons per min.

(Min., Hour)

as determined by test pumping

(Bailing, Test Pumping, Etc.)

DRAWDOWN: 37 ft. after 48 hrs.

pumping at 10 gal. per minute.


REMARKS:

8 1/2" bit, down to 153
6 1/2" bit, down to 192

LOCATION OF WELL

[Show location in Section Plat]

Elev. 1104.5



E 1/2 NE NE 1 Sec.

T. 18 S., R. 17

County FRANKLIN