

1 LOCATION OF WATER WELL
 County: Marion Fraction: NE 1/4 SE 1/4 NE 1/4 Section Number: 2 Township Number: T 18 S Range Number: R 4 E

Distance and direction from nearest town or city? 1.6 mi N - .5 mi E from Lincolnville, Ks
 Street address of well if located within city?

2 WATER WELL OWNER: Mrs. Anna Ecklund
 RR#, St. Address, Box #: RR # 1 Board of Agriculture, Division of Water Resources
 City, State, ZIP Code: Burdick, Kansas 66838 Application Number:

3 DEPTH OF COMPLETED WELL: 96 ft. Bore Hole Diameter: 9 in. to 96 ft. and in. to ft.
 Well Water to be used as:
 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 11 Injection well
 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well
 Well's static water level: 34 ft. below land surface measured on 1 month 8 day 81 year
 Pump Test Data: Well water was 64 ft. after 1/4 hours pumping 18 gpm
 Est. Yield 40 Plus gpm: Well water was ft. after hours pumping gpm

4 TYPE OF BLANK CASING USED:
 1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) Welded
 2 PVC 4 ABS 7 Fiberglass Threaded
 Blank casing dia: 5 in. to 56 ft. Dia in. to ft. Dia in. to ft. Dia in. to ft. Dia
 Casing height above land surface: 15 in. weight 216.603 lbs./ft. Wall thickness or gauge No: 15/64 in.
 TYPE OF SCREEN OR PERFORATION MATERIAL:
 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)
 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)
 Screen or Perforation Openings Are:
 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 11 None (open hole)
 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes
 7 Torch cut 10 Other (specify)
 Screen-Perforation Dia: 5 in. to 96 ft. Dia in. to ft. Dia in. to ft. Dia
 Screen-Perforated Intervals: From 56 ft. to 96 ft. From ft. to ft. From ft. to ft.
 Gravel Pack Intervals: From 60 ft. to 96 ft. From ft. to ft. From ft. to ft.

5 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other
 Grouted Intervals: From 0 ft. to 60 ft. From 1 part Cement - 1 part Sand ft. to ft.
 What is the nearest source of possible contamination:
 1 Septic tank 4 Cess pool 7 Sewage lagoon 10 Fuel storage 14 Abandoned water well
 2 Sewer lines 5 Seepage pit 8 Feed yard 11 Fertilizer storage 15 Oil well/Gas well
 3 Lateral lines 6 Pit privy 9 Livestock pens 12 Insecticide storage 16 Other (specify below) Clear Creek
 Direction from well: N. How many feet: 247 ? Water Well Disinfected? Yes No
 Was a chemical bacteriological sample submitted to Department? Yes No If yes, date sample was submitted: 1 month 19 day 81 year Pump Installed? Yes No
 If Yes: Pump Manufacturer's name: Red Jacket Model No: 50R1CR4BC HP: 1/2 Volts: 220
 Depth of Pump Intake: 88 ft. Pumps Capacity rated at: 11 gal./min.
 Type of pump: 1 Submersible 2 Turbine 3 Jet 4 Centrifugal 5 Reciprocating 6 Other

6 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed (2) reconstructed, or (3) plugged under my jurisdiction and was completed on 1 month 8 day 81 year
 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 161
 This Water Well Record was completed on 1 month 26 day 81 year under the business name of Benda Drilling by (signature) Paul W. Benda

LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
	0	2	Top Soil Black	82	96	Shale Med. Blue
	2	11	Clay Med. yellow			
	11	17	Limestone Porious			
	17	24	Clay Med. yellow			
	24	35	Shale Med. Blue			
	35	42	Clay Brick Red			
	42	45	Sand Fine Water			
	45	62	Lime Wery Hard			
	62	67	Sand & Blue Shale			
	67	75	Shale Med. Blue			
ELEVATION:	75	82	Sandstone Med			

Depth(s) Groundwater Encountered 1. 42 ft. 2. 75 ft. 3. ft. 4. ft. (Use a second sheet if needed)

INSTRUCTIONS: Use typewriter or ball point pen, please press firmly and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Water Well Contractors, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.

OFFICE USE ONLY
 T
 18
 R
 4
 E
 SEC.
 NE 1/4
 SE 1/4
 NE 1/4