

"Ask the man who has had us drill!"

# JUNGMAH BROS. DRILLING CO.

MUNICIPAL, INDUSTRIAL AND DOMESTIC  
WELLS AND EQUIPMENT

1009 Huntoon

TOPEKA, KANSAS

Phone 3-7991

Log of a well at Waverly, Kansas--August 1954

0-1	soil
1-12	broken lime
12-26	blue lime
26	reduced hole to 8"
26-35	lime
35-43	shale
43-44	lime
44-45	shale
45-67	lime
67-69	slate
96-72	lime
72-80	shale
80-95	lime, white
95-118	green shale shells of lime
118-120	sandy shale
120-125	sandy lime with shale breaks
125-140	sandy shale
140-155	shale with streaks of sand
155-170	sand, hard
170-175	sandy shale
175-176	lime, white
176-180	sand
180-185	sand streaks of slate
185-197	shale
197-199	lime
199-205	sandy lime (set pump & pumped app. 2 gpm)
205-215	sand with hard streaks in it
215-220	sand, very hard
220-227	sand with hard and soft places
227-228	shale

Test pumping produced a maximum of 10 gpm.

A six inch casing with packer was set at 199 to stop cave-in from 185-197.

Another packer was set at 26 feet for cement seal.