

Sent to BWS

1-15-79

8-22-79

9

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well: County Coffey Fraction SE 1/4 SE 1/4 NE 1/4 Section number 12 Township number T 20 Range number R 16 E 9

2. Distance and direction from nearest town or city: 4 1/4 S + 1 E Street address of well location if in city: OF WAVERLY

3. Owner of well: ANDERSON CO. RWD # 4 well # 8 R.R. or street: RR 1 City, state, zip code: Westphalia, Ks. 66093

4. Locate with "X" in section below: Sketch map:

6. Bore hole dia. 18 in. Completion date 12-18-78
Well depth 240 ft.

7. Cable tool Rotary Driven Dug
 Hollow rod Jetted Bored Reverse rotary

8. Use: Domestic Public supply Industry
 Irrigation Air conditioning Stock
 Lawn Oil field water Other

9. Casing: Material PVC Height: above or below
Threaded Welded Surface 29 in.
RMP PVC 9L Weight 5.58 lbs./ft.
Dia. 8 in. to 240 ft. depth Wall Thickness: inches or
Dia. in. to ft. depth gage No. 332

5. Type and color of material	From	To
Top soil	0	2
Clay, Brown	2	10
Shale, grey	10	42
Limestone, grey, tan	42	110
Sandy shale, grey	110	116
Sand Rock grey	116	125
Sandy shale	125	140
Sandstone grey	140	195
Sandy shale, grey	195	240

10. Screen: Manufacturer's name PUMPCO MRE
Type PVC Dia. 8
Slot gauge .080 Length 90
Set between 160 ft. and 240 ft.
Gravel pack? Size range of material 1/2 x 1/8

11. Static water level: 146 ft. below land surface Date 12-18-78 mo./day/yr.

12. Pumping level below land surfaces:
 ft. after hrs. pumping g.p.m.
 ft. after hrs. pumping g.p.m.
Estimated maximum yield 25 g.p.m.

13. Water sample submitted: Yes No Date 6-10-78 mo./day/yr.

14. Well head completion: Pitless adapter 24 inches above grade

15. Well grouted?
With: Neat cement Bentonite Concrete
Depth: From 0 ft. to 25 ft.

16. Nearest source of possible contamination: ft. 300 Direction S Type DRAINAGE
Well disinfected upon completion? Yes No

17. Pump: Not installed
Manufacturer's name JACUZZI
Model number 154B HP 1 Volts 230
Length of drop pipe 220 ft. capacity 10 g.p.m.
Type: Submersible Turbine
 Jet Reciprocating
 Centrifugal Other

18. Elevation: Topography: Hill Slope Upland Valley

19. Remarks: we will install concrete slab
Shelter of Griffith & Shelter
Acc. & Eng. #13 sample taken at time of Test well

20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.
STRADER Drilling Co. License No. 182
Business name RR Holton, Ks
Address
Signed Date 12-21-78
Authorized representative

R 20
E 16
W 12
S 9
NE 16

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5