

Sent 4-25 77
 Sent again 9/30/77

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
 KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
 (Water well Contractors)
 Topeka, Kansas 66620

1. Location of well:		County MAVION	Fraction NE 1/4 NW 1/4 NE 1/4	Section number 9	Township number T 22 S R 3 E	Range number 3 E
2. Distance and direction from nearest town or city: 3/4 mile S Peabody			3. Owner of well: LOWENANCE JURY R.R. or street: RR # 2 Peabody, Kns 66866 City, state, zip code:			
4. Locote with "X" in section below:		Sketch map:			6. Bore hole dia. 10 in. Completion date 3/7/77 Well depth 58 ft.	
					7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
5. Type and color of material		From	To	8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Loam & clay		0	5	9. Casing: Material plastic Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight 2.28 lbs./ft. Dia. 5 in. to 58 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 220.295		
brown clay		5	10	10. Screen: Manufacturer's name Robin-Tech - own slot Type PVC Dia. 5" Slot/gauze #046 Length 20' Set between 38 ft. and 58 ft. <input type="checkbox"/> ft. and <input type="checkbox"/> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material 1/8-1/4		
hard brown-grey clay		10	20	11. Static water level: <input type="checkbox"/> no./day/yr. 37 ft. below land surface Date 3/7/77		
hard dark brown shale		20	22	12. Pumping level below land surfaces: 47 ft. after 1 hrs. pumping 15 g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield 15 g.p.m.		
grey-brown clay		22	34	13. Water sample submitted: <input type="checkbox"/> mo./day/yr. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date 3/22/77		
dark brown rock (sm fault)		34	35	14. Well head completion: <input type="checkbox"/> Pitless adapter 12 Inches above grade		
grey-brown shale-semi soft		35	45	15. Well grouted? <input checked="" type="checkbox"/> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 10 ft. to 0 ft.		
dark grey shale-semi-soft		45	57	16. Nearest source of possible contamination: ST ft. 15 Direction N Type Sewer Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
fault			58	17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name Unknown Model number <input type="checkbox"/> HP 1/2 Volts 220 Length of drop pipe 53' ft. capacity 2 g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input checked="" type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
(Use a second sheet if needed)				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. PAUL'S INC #175 Business name License No. Address Box 26 Hesston, Kns Signed Paul B... Date 3/24/77 Authorized representative		
18. Elevation:	19. Remarks: Installed owners old pumping system		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. PAUL'S INC #175 Business name License No. Address Box 26 Hesston, Kns Signed Paul B... Date 3/24/77 Authorized representative			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5