

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>HARVEY</b>	Fraction <b>SE 1/4 NE 1/4 NW 1/4</b>	Section number <b>8</b>	Township number T <b>23</b> S R	Range number 1 <b>(E/W)</b>
2. Distance and direction from nearest town or city: <b>Lot #1 - blk. 4A</b>			3. Owner of well: <b>FRANK STUCKY</b>			
Street address of well location if in city: <b>201-W-22<sup>nd</sup> St. N. Newton</b>			R.R. or street: <b>812 LOGAN ST.</b>			
			City, state, zip code: <b>NEWTON, KANSAS</b>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <b>14</b> in. Completion date _____		
				Well depth _____ ft. <b>3-7-79</b>		
				7. Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
5. Type and color of material		From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input checked="" type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input checked="" type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
<b>LOAM</b>		<b>0</b>	<b>5</b>	9. Casing: Material <b>Plastic</b> Height <b>Above</b> or below _____		
<b>SURFACE SAND (loose)</b>		<b>6</b>	<b>9</b>	Threaded _____ Welded _____ Surface <b>12</b> in.		
<b>Light BROWN CLAY</b>		<b>9</b>	<b>14</b>	RMP _____ PVC <input checked="" type="checkbox"/> Weight <b>3.58</b> lbs./ft.		
<b>SAND - MED - Sharp</b>		<b>14</b>	<b>20</b>	Dia. <b>6</b> in. to <b>48</b> ft. depth   Wall Thickness: inches or _____		
<b>Grey CLAY</b>		<b>20</b>	<b>29</b>	Dia. _____ in. to _____ ft. depth   gage No. <b>280</b>		
<b>SANDY MIXED w/ CLAY</b>		<b>29</b>	<b>35</b>	10. Screen: Manufacturer's name _____		
<b>White HARD rock</b>		<b>35</b>	<b>37</b>	Type <b>plastic</b> - <b>open slot</b>		
<b>GREEN-Grey to DARK WEIL. SHALE</b>		<b>37</b>	<b>48</b>	Type <b>PVC</b> Dia. <b>6"</b>		
				Slot/gauze <b>1046</b> Length <b>15'</b>		
				Set between <b>15</b> ft. and <b>20</b> ft.		
				<b>28</b> ft. and <b>38</b> ft.		
				Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>1/8-1/4</b>		
				11. Static water level: _____ mo./day/yr.		
				<b>8 1/2</b> ft. below land surface Date <b>3-9-79</b>		
				12. Pumping level below land surfaces:		
				<b>15</b> ft. after <b>12</b> hrs. pumping <b>18</b> g.p.m.		
				_____ ft. after _____ hrs. pumping _____ g.p.m.		
				Estimated maximum yield <b>20/30</b> g.p.m.		
				13. Water sample submitted: _____ mo./day/yr.		
				Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date _____		
				14. Well head completion:		
				<input checked="" type="checkbox"/> Pitless adapter <b>12</b> inches above grade		
				15. Well grouted? <input checked="" type="checkbox"/>		
				With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete		
				Depth: From <b>10</b> ft. to <b>0</b> ft.		
				16. Nearest source of possible contamination: <b>house</b>		
				ft. <b>45</b> Direction <b>WEST</b> Type <b>sewerline</b>		
				Well disinfected upon completion? _____ Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>		
				17. Pump: <input checked="" type="checkbox"/> Not installed		
				Manufacturer's name _____		
				Model number _____ HP _____ Volts _____		
				Length of drop pipe _____ ft. capacity _____ g.p.m.		
				Type:		
				<input type="checkbox"/> Submersible <input type="checkbox"/> Turbine		
				<input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating		
				<input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
18. Elevation:		19. Remarks:		20. Water well contractor's certification:		
Topography:				This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.		
<input type="checkbox"/> Hill				<b>PAUL'S INC. #175</b>		
<input type="checkbox"/> Slope				Business name _____ License No. _____		
<input type="checkbox"/> Upland				Address <b>HEGSTON KNS</b>		
<input type="checkbox"/> Valley				Signed <b>Paul Burdick</b> Date <b>3/21/79</b>		
				Authorized representative		

T  
R  
E  
S  
E  
C  
1/4  
1/4  
1/4  
1/4