

[1] LOCATION OF WATER WELL:		Fraction	Township Number	Range Number	
County: Harvey	NW ¼ SW ¼ SE ¼	21	T 23 S	R 1 E W	
Distance and direction from nearest town or city street address of well if located within city? 1100 S. Kansas Street, Newton, KS MW 2					
[2] WATER WELL OWNER:					
City of Newton RR#, St. Address, Box # : Box 426 City, State, ZIP Code : Newton, KS 67114		Board of Agriculture, Division of Water Resources Application Number: 			
[3] LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		[4] DEPTH OF COMPLETED WELL: <u>28</u> ft. ELEVATION:			
A square divided into four smaller squares labeled NW, NE, SW, and SE. A dashed horizontal line runs through the middle, and a dashed vertical line runs down the center. An 'X' is drawn in the bottom-left corner (SW).		Depth(s) Groundwater Encountered 1. <u>18</u> ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL <u>15.48</u> ft. below land surface measured on mo/day/yr <u>07-01-92</u>			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield gpm; Well water was ft. after hours pumping gpm			
		Bore Hole Diameter <u>7 5/8</u> in. to <u>28</u> in., and in. to ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well			
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)			
		2 Irrigation 4 Industrial 7 Lawn and garden only ☒ Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes.....No... ☒ mitted Water Well Disinfected? Yes No ☒			
[5] TYPE OF BLANK CASING USED:					
Blank casing diameter 2 in. to 8 ft., Dia in. to ft., Dia in. to ft.					
Casing height above land surface 0 in., weight lbs./ft. Wall thickness or gauge No. Sch. 40					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement					
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify)					
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot ☒ Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)					
2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes					
3 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From 8 ft. to 28 ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From 6 ft. to 28 ft., From ft. to ft.					
[6] GROUT MATERIAL: 1 Neat cement ☒ Cement grout ☒ Bentonite 4 Other					
Grout intervals: From 0 ft. to 2 ft., From 2 ft. to 6 ft., From ft. to ft.					
What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy ☒ Fuel storage 10 Livestock pens 14 Abandoned water well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 15 Oil well/Gas well					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage 16 Other (specify below)					
Direction from well? South How many feet? 160					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	Silty clay, black			Flush Mount cover KDHE Site ID # 00097608
2	4	Clay, Dark red			
4	11	Sandy clay, tan			
11	13	Sandy clay, green			
13	28	Sand, pink, fine to medium			
[7] CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) ... <u>06-18-92</u> ... and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 527 This Water Well Record was completed on (mo/day/yr) <u>07-07-92</u> under the business name of _____ by (signature) <u>Pete Rohl</u>					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY AND PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.					