


CLARKE WELL & EQUIPMENT, INC.

WELL RECORD DESIGN & CONSTRUCTION SHEET



SECTION

JOB NUMBER 3679
 WELL OWNER City of Wichita WELL NO. H9
 WELL USE Piezometer APPROPRIATION NO. _____
 LOCATION SE 1/4 SE 1/4 SW 1/4, SECTION NO. 29
 T 23 S, R 2 W/E Harvey COUNTY Kansas
90 FSL, 2952 FEL State

SIZE HOLE 6 "DIA.
 SIZE CASING 2 " DIA .218 WALL; WT. .96 LBS/FT PVC MATERIAL
 SIZE SCREEN 2 " DIA .218 WALL PVC MATERIAL .030 Mill SLOT/HOLE

FORMATION LOG. From test no. from to			Formation Thickness	From ground level	From	To	Fig.
0	4	Topsoil		Casing	0	156	156
4	9	Clay, brown, hard		Screen	156	166	10
9	28	Sand and gravel, coarse, medium, fine					
28	44	Clay, black and gray, hard					
44	54	Clay, gray, soft					
54	61	Clay, green, soft					
61	66	Sand, medium and fine					
66	83	Clay, green, soft					
83	88	Clay, white and brown, soft					
88	106	Sand, medium and fine					
106	118	Clay, green, hard					
118	136	Clay, white, hard					
136	144	Sand, medium and fine					
144	149	Clay, white, hard					
149	174	Sand, medium and fine		CASING LEFT ABOVE GROUND			2
174	175	Clay, white, hard		TOTAL CASING & SCREEN			160

STATIC WATER LEVEL 54.8 CHLORINATE none QUANTITY USED
 From ground level

GRAVEL PACK ANNULAR SEAL
154 TO 175 0 TO 154 Bentonite Holeplug
 TO TO

WHAT IS THE NEAREST SOURCE OF POSSIBLE CONTAMINATION None known
 DIRECTION FROM WELL _____ HOW MANY FEET _____
 DESIGNED BY _____ DRILLED BY Edward Cass DATE 5-9-97