


# CLARKE WELL & EQUIPMENT, INC.

## WELL RECORD DESIGN & CONSTRUCTION SHEET



JOB NUMBER 3679  
 WELL OWNER City of Wichita WELL NO. H11  
 WELL USE Piezometer APPROPRIATION NO.           
 LOCATION NE 1/4 NE 1/4 NW 1/4, SECTION NO. 32  
 T 23 S, R 2 W/E Harvey COUNTY Kansas  
5096 FSL, 2662 FEL State

SIZE HOLE 6 "DIA.  
 SIZE CASING 2 " DIA .218 WALL; WT. .96 LBS/FT PVC MATERIAL  
 SIZE SCREEN 2 " DIA .218 WALL PVC MATERIAL .030 Mill SLOT/NO. 8

FORMATION LOG. From test no. from to			Formation Thickness	From ground level	From	To	Ftg.
0	2	Topsoil		Casing	0	142	142
2	12	Clay, brown, hard		Screen	142	152	10
12	31	Sand and gravel, coarse, medium, fine					
31	57	Clay, gray and black, hard					
57	59	Sand, medium and fine					
59	64	Clay, green, soft					
64	70	Sand, medium and fine					
70	71	Clay, green, hard					
71	74	Sand, medium and fine					
74	98	Clay, green, soft, sand streak					
98	104	Clay, green, hard					
104	130	Clay, white and green, hard					
130	134	Clay, gray, soft					
134	170	Sand, medium and fine					
				CASING LEFT ABOVE GROUND			2
				TOTAL CASING & SCREEN			154

STATIC WATER LEVEL 53.8 CHLORINATE None QUANTITY USED  
 From ground level

GRAVEL PACK ANNULAR SEAL  
140 TO 170 0 TO 140 Bentonite Holeplug  
         TO                   TO         

WHAT IS THE NEAREST SOURCE OF POSSIBLE CONTAMINATION None known  
 DIRECTION FROM WELL          HOW MANY FEET           
 DESIGNED BY          DRILLED BY Edward Cass DATE 5-8-97