


CLARKE WELL & EQUIPMENT, INC.

WELL RECORD

DESIGN & CONSTRUCTION SHEET



JOB NUMBER 3679
 WELL OWNER City of Wichita WELL NO. H12
 WELL USE Piezometer APPROPRIATION NO.
 LOCATION SE 1/4 SE 1/4 SW 1/4, SECTION NO. 29
 T 23 S, R 2 W/E Harvey COUNTY Kansas
40 FSL, 2655 FEL State

SIZE HOLE 6 "DIA.

SIZE CASING 2 " DIA .218 WALL; WT. .96 LBS/FT PVC MATERIAL

SIZE SCREEN 2 " DIA .218 WALL PVC MATERIAL .030 M111 SLOT/NOSE

FORMATION LOG. From test no. from to			Formation Thickness	From ground level	From	To	Ftg.
0	2	Topsoil		Casing	0	137	137
2	11	Clay, brown, hard		Screen	137	147	10
11	28	Sand and gravel, coarse, medium, fine					
28	55	Clay, dark gray, hard					
55	64	Clay, green, hard					
64	65	Sand, medium, fine					
65	68	Clay, green, hard					
68	69	Sand, medium and fine					
69	89	Clay, green, hard					
89	96	Sand, medium and fine					
96	114	Clay, green, hard, sand streaks					
114	118	Clay, green and white, hard					
118	121	Sand, medium and fine					
121	129	Clay, green and white, hard					
129	155	Sand, medium and fine		CASING LEFT ABOVE GROUND			2
155	156	Clay, brown and green, soft		TOTAL CASING & SCREEN			149

STATIC WATER LEVEL 52.05 CHLORINATE none QUANTITY USED
 From ground level

GRAVEL PACK

ANNULAR SEAL

135 TO 156 0 TO 135 Bentonite Holeplug
 TO TO

WHAT IS THE NEAREST SOURCE OF POSSIBLE CONTAMINATION None known

DIRECTION FROM WELL HOW MANY FEET

DESIGNED BY DRILLED BY Edward Cass DATE 5-5-97