

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: EDWARDS NW 1/4 NW 1/4 NE 1/4 15 T 23 S R 20 E

Distance and direction from nearest town or city street address of well if located within city?
 FROM OFFERLE - 7 NORTH, 2 EAST, 4 NORTH & 1/2 EAST

2 WATER WELL OWNER: D & D PUMP
 RR#, St. Address, Box #: X BOB DAVIS -56 HIWAY WES Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SUBLETTE, KS 67877- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

		X	
NW	NE		
SW	SE		

4 DEPTH OF COMPLETED WELL 245 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 127 ft. below land surface measured on no/day/yr 06/02/04
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 35 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9 in. to 245 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 245 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 200 ft. to 240 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 245 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout intervals: From 1 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 05 CLAY 02 FINE SAND			
20	40	10 FINE-MEDSAND			
40	60	10 FINE-MEDSAND 05 CLAY 07 BLUE SHALE			
60	120	07 BLUE SHALE 05 CLAY			
120	140	36 BLUE CLAY 16 GRAY CLAY			
140	180	16 GRAY CLAY 29 SANDSTONE			
180	220	29 SANDSTONE			
220	240	29 SANDSTONE 26 RED CLAY			

RECEIVED
 OCT 27 2004
 BUREAU OF WATER

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (no/day/year) 06/03/04 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 06/24/04
 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Judith Cwik*