

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: FORD NE 1/4 NE 1/4 SE 1/4 14 T 25 S R 22 E

Distance and direction from nearest town or city street address of well if located within city?  
 FROM SPEARVILLE ON HIGHWAY 50 - 3 MILES EAST & 3/4 NORTH

2 WATER WELL OWNER: STRECKER, MELVIN  
 RR#, St. Address, Box #: 12863 FOOTHILL RD.  
 City, State, ZIP code: SPEARVILLE, KS 67876- Board of Agriculture, Division of Water Resources  
 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4
W	NW	NE	E
4	SW	SE	

4 DEPTH OF COMPLETED WELL 425 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 127 ft. below land surface measured on no/day/yr 02/28/06  
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 50 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 10 in. to 425 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: DOMESTIC  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: CERTA LOC CASIN CASING JOINTS: CERTA-LOC  
 Blank casing diameter 5 in. to 425 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 17  
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 320 ft. to 420 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 25 ft. to 75 ft., From 0 ft. to 0 ft.  
 From 82 ft. to 425 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE  
 Grout Intervals: From 5 ft. to 25 ft., From 75 ft. to 82 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 05 CLAY 35 CALACHIE			
20	40	35 CALACHIE 08 ROCK LAYERS 12 SANDROCK LAYER			
40	60	27 ROCK 21 Limestone 07 BLUE SHALE			
60	80	07 BLUE SHALE			
80	120	36 BLUE CLAY			
120	140	16 GRAY CLAY			
140	160	16 GRAY CLAY 26 RED CLAY			
160	180	16 GRAY CLAY 11 BROWN CLAY			
180	200	16 GRAY CLAY 29 SANDSTONE			
200	220	16 GRAY CLAY 29 SANDSTONE 19 LAYERS			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (no/day/year) 03/03/06 and this record is true to the best of my knowledge and belief. Kansas  
 Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 03/13/06  
 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Justin Cuck*

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: FORD	NE 1/4 NE 1/4 SE 1/4	14	T 25 S	R 22 E

2 WATER WELL OWNER:	STRECKER, MELVIN	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	12863 FOOTHILL RD.	Application Number:
City, State, ZIP code :	SPEARVILLE, KS 67876-	

FROM	TO	LITHOLOGIC LOG
220	240	29 SANDSTONE 27 ROCK
240	260	29 SANDSTONE
260	280	29 SANDSTONE 16 GRAY CLAY
280	320	16 GRAY CLAY 26 RED CLAY
320	420	29 SANDSTONE
420	460	29 SANDSTONE 16 GRAY CLAY 19 LAYERS

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION:	This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/03/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 03/13/06 under the business name of JOE'S WELL SERVICE, INC. by (signature) Judith Crick
--	---