

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

1 LOCATION OF WATER WELL: County: SEDGWICK	Fraction ¼ SE ¼ SE ¼ SW ¼	Section Number 27	Township No. T 26 S	Range Number R 1 ☒ E ☐ W			
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ 2100 E. 37TH ST. NORTH, WICHITA, KS 67219		Global Positioning System (GPS) information: Latitude: 37.752600° (in decimal degrees) Longitude: -97.309226° (in decimal degrees) Elevation: Datum: ☒ WGS 84, ☐ NAD 83, ☐ NAD 27 Collection Method: ☐ GPS unit (Make/Model:) ☒ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☒ 5-15 m, ☐ >15 m					
2 WATER WELL OWNER: CHEVRON EMC (BR1Y-RM. 3424) RR#, Street Address, Box #: 6111 BOLLINGER CANYON RD. City, State, ZIP Code : SAN RAMON, CA 94583							
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N W <table border="1" style="border-collapse: collapse; text-align: center;"> <tr> <td style="padding: 5px;">NW</td> <td style="padding: 5px;">NE</td> </tr> <tr> <td style="padding: 5px;">SW</td> <td style="padding: 5px;">SE</td> </tr> </table> E S S -----1 mile-----	NW	NE	SW	SE	4 DEPTH OF COMPLETED WELL 33 ft. Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL..... ft. below land surface measured on mo/day/yr..... Pump test data: Well water was..... ft. after..... hours pumping..... gpm EST. YIELD..... gpm. Well water was..... ft. after..... hours pumping..... gpm Bore Hole Diameter 8 in. to 33 ft., and in. to ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☐ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☒ Monitoring well → P-15-D Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted..... Water well disinfected? ☐ Yes ☒ No		
NW	NE						
SW	SE						
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☐ Glued ☐ Clamped ☐ Welded ☒ Threaded Casing diameter 2 in. to 23 ft., Diameter in. to ft., Diameter in. to ft. Casing height above land surface..... in., Weight lbs./ft., Wall thickness or gauge No. SCH 40 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☒ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☐ Saw cut ☐ Other (specify) SCREEN-PERFORATED INTERVALS: From 33 ft. to 23 ft., From ft. to ft. From ft. to ft., From ft. to ft. SAND GRAVEL PACK INTERVALS: From 33 ft. to 21 ft., From ft. to ft. From ft. to ft., From ft. to ft.							
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other Grout Intervals: From 21 ft. to 2 ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well Direction from well (ON-SITE)..... Distance from well ON-SITE SOURCE.....							
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS		
0	3.5'	FILL					
3.5'	4.5'	SAND					
4.5'	6.5'	SELTY CLAY					
6.5'	8'	SAND					
8'	12'	CLAYEY SELT					
12'	19'	SELTY CLAY					
19'	26'	SANDY SELT / SELTY SAND					
		(GRAVEL @ 23.9' + 25.7')					
26'	32'	SELT / SELTY SAND / CLAYEY SELT					
32'	33'	SHALE					
					(REDI JOB #102028)		
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 12/16/10 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 788 This Water Well Record was completed on (mo/day/year) 1/24/11 under the business name of ROBERTS ENV. DRILLING, INC. by (signature) Charles Roberts							
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .							