

WATER WELL RECORD Form WWC-5

Division of Water
Resources App. No.

Well ID IW-25

☒ Original Record ☐ Correction ☐ Change in Well Use

1 LOCATION OF WATER WELL: County: Sedgwick		Fraction SW ¼ NE ¼ SW ¼ SE ¼	Section Number 27	Township Number T 26 S	Range Number R 1 ☒ E ☐ W
2 WELL OWNER: Last Name: First: Business: USD 259 School Services Center Address: 3850 N. Hydraulic St. City: Wichita State: KS ZIP: 67219		Street or Rural Address where well is located (if unknown, distance and direction from nearest town or intersection): If at owner's address, check here: ☒			
3 LOCATE WELL WITH "X" IN SECTION BOX: N W E S 1 mile	4 DEPTH OF COMPLETED WELL: 29 ft. Depth(s) Groundwater Encountered: 1) 20 ft. 2) ft. 3) ft. or 4) ☐ Dry Well WELL'S STATIC WATER LEVEL: 17.87 ft. ☒ below land surface, measured on (mo-day-yr) 01/29/2016 ☐ above land surface, measured on (mo-day-yr) Pump test data: Well water was ft. after hours pumping gpm Well water was ft. after hours pumping gpm Estimated Yield: gpm Bore Hole Diameter: 3.6 in. to 30 ft. and in. to ft.		5 Latitude: 37.754958 (decimal degrees) Longitude: 97.314892 (decimal degrees) Datum: ☐ WGS 84 ☒ NAD 83 ☐ NAD 27 Source for Latitude/Longitude: ☐ GPS (unit make/model:) (WAAS enabled? ☐ Yes ☐ No) ☒ Land Survey ☐ Topographic Map ☐ Online Mapper:		
	6 Elevation: 1331.48 ft. ☒ Ground Level ☐ TOC Source: ☒ Land Survey ☐ GPS ☐ Topographic Map ☐ Other				

7 WELL WATER TO BE USED AS:

1. Domestic: ☐ Household ☐ Lawn & Garden ☐ Livestock	5. ☐ Public Water Supply: well ID	10. ☐ Oil Field Water Supply: lease
2. ☐ Irrigation	6. ☐ Dewatering: how many wells?	11. Test Hole: well ID
3. ☐ Feedlot	7. ☐ Aquifer Recharge: well ID	☐ Cased ☐ Uncased ☐ Geotechnical
4. ☐ Industrial	8. ☐ Monitoring: well ID	12. Geothermal: how many bores?
	9. Environmental Remediation: well ID IW-25	a) Closed Loop ☐ Horizontal ☐ Vertical
	☐ Air Sparge ☐ Soil Vapor Extraction	b) Open Loop ☐ Surface Discharge ☐ Inj. of Water
	☐ Recovery ☒ Injection	13. ☐ Other (specify):

Was a chemical/bacteriological sample submitted to KDHE? ☐ Yes ☒ No If yes, date sample was submitted:
Water well disinfected? ☐ Yes ☒ No

8 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☐ Glued ☐ Clamped ☐ Welded ☒ Threaded
Casing diameter 1.5 in. to 19 ft., Diameter in. to ft., Diameter in. to ft.
Casing height above land surface 0 in. Weight lbs./ft. Wall thickness or gauge No. 40
TYPE OF SCREEN OR PERFORATION MATERIAL:
☐ Steel ☐ Stainless Steel ☐ Fiberglass ☒ PVC ☐ Other (Specify)
☐ Brass ☐ Galvanized Steel ☐ Concrete tile ☐ None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:
☐ Continuous Slot ☒ Mill Slot ☐ Gauze Wrapped ☐ Torch Cut ☐ Drilled Holes ☐ Other (Specify)
☐ Louvered Shutter ☐ Key Punched ☐ Wire Wrapped ☐ Saw Cut ☐ None (Open Hole)
SCREEN-PERFORATED INTERVALS: From 19 ft. to 29 ft., From ft. to ft., From ft. to ft.
GRAVEL PACK INTERVALS: From 17.5 ft. to 29 ft., From ft. to ft., From ft. to ft.

9 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☒ Other Bentonite Cement (1-15.3')
Grout Intervals: From 1 ft. to 15.3 ft., From 15.3 ft. to 17.5 ft., From ft. to ft.

Nearest source of possible contamination:
☐ Septic Tank ☐ Lateral Lines ☐ Pit Privy ☐ Livestock Pens ☐ Insecticide Storage
☐ Sewer Lines ☐ Cess Pool ☐ Sewage Lagoon ☐ Fuel Storage ☐ Abandoned Water Well
☐ Watertight Sewer Lines ☐ Seepage Pit ☐ Feedyard ☐ Fertilizer Storage ☐ Oil Well/Gas Well
☐ Other (Specify)
Direction from well? Distance from well? ft.

10 FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS
0	0.5	Asphalt			
0.5	0.8	Fill, blk, fn to med sand, asphalt			
0.8	12	Lean Clay, dk brn to blk to med brn			
12	20	Lean Clay, med brn, vf sand			
20	20.2	Sand, med brn, fn to med			
20.2	23.6	Clayey Silt, yllw grn to brn			
23.6	28.2	Silt and Wthrd Siltstone, grn gry to med br	Notes:		
28.2	30	Siltstone, dk gry			

11 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo-day-year) 01/29/2016 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 531 This Water Well Record was completed on (mo-day-year) 03/18/2016 under the business name of GSI Engineering, LLC

Chel Ceb



Legend

 Well Location

 Permeable Reactive Barrier (PRB)

Notes:
1. Site features, property boundaries and well locations are approximate and are not of legal land survey.
2. Basemap source: Golder Associates, drawing titled: "Potentiometric Surface Elevation Map April 2013", dated August, 26, 2013, Figure Number 1, File No. 12384321, Revision 1 (Draft) and modified by Geosyntec in December 2014.
3. Imagery source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AEX, Getmapping, Aerogrid, IGN, IGP, swisstopo, and the GIS User Community.
4. Coordinate system is NAD83, KS South, State Plane Zone 1502, US Survey Foot format

Location	Easting	Northing
IW-12	1654956.71	1710758.11
IW-13	1654939.73	1710760.41
IW-14	1654927.02	1710760.08
IW-15	1654923.79	1710742.45
IW-16	1654904.99	1710740.19
IW-17	1654875.60	1710700.21
IW-18	1654883.78	1710720.26
IW-19	1654864.15	1710720.65
IW-20	1654883.46	1710739.54
IW-21	1654885.60	1710759.52
IW-22	1654906.96	1710759.64
IW-23	1654902.25	1710779.25
IW-24	1654921.84	1710779.29
IW-25	1654941.56	1710781.08
IW-26	1654961.82	1710778.26
MW-28	1654846.54	1710677.86
MW-29	1654564.13	1710579.36
MW-30	1654564.26	1710541.52
MW-31	1654564.64	1710500.84
MW-32	1654565.31	1710451.32
MW-33	1654769.45	1710692.46
MW-34	1654723.11	1710550.71
MW-35	1654932.63	1710755.43

150750150 Feet

Well Installation Locations

USD 259 School Service Center, Wichita, Kansas

Geosyntec[®]
consultants

Guelph

Figure

1

April 2016