

WATER WELL RECORD Form WWC-5

Division of Water
Resources App. No.

Well ID

MW-29

☒ Original Record ☐ Correction ☐ Change in Well Use

1 LOCATION OF WATER WELL:

County: Sedgwick

Fraction
SE ¼ NW ¼ SW ¼ SW ¼

Section Number
27

Township Number
T 26 S

Range Number
R 1 ☒ E ☐ W

2 WELL OWNER: Last Name:

First:

Street or Rural Address where well is located (if unknown, distance and direction from nearest town or intersection): If at owner's address, check here: ☒

Business: USD 259 School Services Center

Address: 3850 N. Hydraulic St.


Address:

City: Wichita

State: KS ZIP: 67219

3 LOCATE WELL WITH "X" IN SECTION BOX:

N



S

1 mile

4 DEPTH OF COMPLETED WELL:

Depth(s) Groundwater Encountered: 1) 26 ft.

2) ft. 3) ft. or 4) Dry Well

WELL'S STATIC WATER LEVEL: 19.42 ft.

☒ below land surface, measured on (mo-day-yr) 02/18/2016

☐ above land surface, measured on (mo-day-yr)

Pump test data: Well water was ft.

after hours pumping gpm

Well water was ft.

after hours pumping gpm

Estimated Yield: gpm

Bore Hole Diameter: 3.6 in. to 32 ft. and

in. to ft.

5 Latitude: 37.754417 (decimal degrees)

Longitude: 97.316208 (decimal degrees)

Datum: ☐ WGS 84 ☒ NAD 83 ☐ NAD 27

Source for Latitude/Longitude:

☐ GPS (unit make/model: (WAAS enabled? ☐ Yes ☐ No)

☒ Land Survey ☐ Topographic Map

☐ Online Mapper:

6 Elevation: 1330.27 ft. ☐ Ground Level ☒ TOC

Source: ☒ Land Survey ☐ GPS ☐ Topographic Map

☐ Other

7 WELL WATER TO BE USED AS:

1. Domestic:

- ☐ Household
☐ Lawn & Garden
☐ Livestock

2. ☐ Irrigation

3. ☐ Feedlot

4. ☐ Industrial

5. ☐ Public Water Supply: well ID

6. ☐ Dewatering: how many wells?

7. ☐ Aquifer Recharge: well ID

8. ☒ Monitoring: well ID MW-29

9. Environmental Remediation: well ID

☐ Air Sparge ☐ Soil Vapor Extraction

☐ Recovery ☐ Injection

10. ☐ Oil Field Water Supply: lease

11. Test Hole: well ID

☐ Cased ☐ Uncased ☐ Geotechnical

12. Geothermal: how many bores?

a) Closed Loop ☐ Horizontal ☐ Vertical

b) Open Loop ☐ Surface Discharge ☐ Inj. of Water

13. ☐ Other (specify):

Was a chemical/bacteriological sample submitted to KDHE? ☐ Yes ☒ No If yes, date sample was submitted:

Water well disinfected? ☐ Yes ☒ No

8 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☐ Glued ☐ Clamped ☐ Welded ☒ Threaded

Casing diameter 1.5 in. to 22 ft. Diameter in. to ft. Diameter in. to ft.

Casing height above land surface 0 in. Weight lbs./ft. Wall thickness or gauge No. 40

TYPE OF SCREEN OR PERFORATION MATERIAL:

- ☐ Steel ☐ Stainless Steel ☐ Fiberglass ☒ PVC ☐ Other (Specify)
☐ Brass ☐ Galvanized Steel ☐ Concrete tile ☐ None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:

- ☐ Continuous Slot ☒ Mill Slot ☐ Gauze Wrapped ☐ Torch Cut ☐ Drilled Holes ☐ Other (Specify)
☐ Louvered Shutter ☐ Key Punched ☐ Wire Wrapped ☐ Saw Cut ☐ None (Open Hole)

SCREEN-PERFORATED INTERVALS: From 22 ft. to 32 ft. From ft. to ft. From ft. to ft.

GRAVEL PACK INTERVALS: From 19.5 ft. to 32 ft. From ft. to ft. From ft. to ft.

9 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☒ Other Bentonite Cement (1-14.3')

Grout Intervals: From 1 ft. to 14.3 ft. From 14.3 ft. to 19.5 ft. From ft. to ft.

Nearest source of possible contamination:

- ☐ Septic Tank ☐ Lateral Lines ☐ Pit Privy ☐ Livestock Pens ☐ Insecticide Storage
☐ Sewer Lines ☐ Cess Pool ☐ Sewage Lagoon ☐ Fuel Storage ☐ Abandoned Water Well
☐ Watertight Sewer Lines ☐ Seepage Pit ☐ Feedyard ☐ Fertilizer Storage ☐ Oil Well/Gas Well
☐ Other (Specify)

Direction from well? Distance from well? ft.

10 FROM TO LITHOLOGIC LOG FROM TO LITHO. LOG (cont.) or PLUGGING INTERVALS

0 26 Lean Clay, dk brn to blk to med brn, trc sand

26 27 Sand with Clay, brn, med sand

27 28 No Recovery

28 30.5 Sand, prlv qrd, med to crs, clay & silt

30.5 32 Sandy Clay, to gry siltstone

Notes:

11 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo-day-year) 01/25/2016 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 531 This Water Well Record was completed on (mo-day-year) 03/18/2016 under the business name of GSI Engineering, LLC

Send one copy to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.

KS Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-3565.

Visit us at <http://www.kdheks.gov/waterwell/index.html>

KSA 82a-1212

Chal Ceb



Legend

◆ Well Location

■ Permeable Reactive Barrier (PRB)

Notes:

1. Site features, property boundaries and well locations are approximate and are not of legal land survey.
2. Basemap source: Golder Associates, drawing titled: "Potentiometric Surface Elevation Map April 2013", dated August, 26, 2013, Figure Number 1, File No. 12384321, Revision 1 (Draft) and modified by Geosyntec in December 2014.
3. Imagery source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AEX, Getmapping, Aerogrid, IGN, IGP, swisstopo, and the GIS User Community.
4. Coordinate system is NAD83, KS South, State Plane Zone 1502, US Survey Foot format

Location	Easting	Northing
IW-12	1654956.71	1710758.11
IW-13	1654939.73	1710760.41
IW-14	1654927.02	1710760.08
IW-15	1654923.79	1710742.45
IW-16	1654904.99	1710740.19
IW-17	1654875.60	1710700.21
IW-18	1654883.78	1710720.26
IW-19	1654864.15	1710720.65
IW-20	1654883.46	1710739.54
IW-21	1654885.60	1710759.52
IW-22	1654906.96	1710759.64
IW-23	1654902.25	1710779.25
IW-24	1654921.84	1710779.29
IW-25	1654941.56	1710781.08
IW-26	1654961.82	1710778.26
MW-28	1654846.54	1710677.86
MW-29	1654564.13	1710579.36
MW-30	1654564.26	1710541.52
MW-31	1654564.64	1710500.84
MW-32	1654565.31	1710451.32
MW-33	1654769.45	1710692.46
MW-34	1654723.11	1710550.71
MW-35	1654932.63	1710755.43

150 75 0 150 Feet

Well Installation Locations

USD 259 School Service Center, Wichita, Kansas

Geosyntec
consultants

Guelph

April 2016

Figure

1