

WATER WELL RECORD Form WWC-5

Division of Water
Resources App. No.

MW-30

☒ Original Record ☐ Correction ☐ Change in Well Use

Well ID

1 LOCATION OF WATER WELL: County: Sedgwick		Fraction SE ¼ NW ¼ SW ¼ SW ¼	Section Number 27	Township Number T 26 S	Range Number R 1 ☒ E ☐ W
2 WELL OWNER: Last Name: _____ Business: USD 259 School Services Center Address: 3850 N. Hydraulic St. City: Wichita State: KS ZIP: 67219		Street or Rural Address where well is located (if unknown, distance and direction from nearest town or intersection): If at owner's address, check here: ☒			
3 LOCATE WELL WITH "X" IN SECTION BOX: N W E S -----1 mile-----		4 DEPTH OF COMPLETED WELL: 30 ft. Depth(s) Groundwater Encountered: 1) 26.5 ft. 2) ft. 3) ft., or 4) ☐ Dry Well WELL'S STATIC WATER LEVEL: 19.28 ft. ☒ below land surface, measured on (mo-day-yr) 02/18/2016 ☐ above land surface, measured on (mo-day-yr) Pump test data: Well water was ft. after hours pumping gpm Well water was ft. after hours pumping gpm Estimated Yield: gpm Bore Hole Diameter: 3.6 in. to 32 ft. and in. to ft.		5 Latitude: 37.754314 (decimal degrees) Longitude: 97.316208 (decimal degrees) Datum: ☐ WGS 84 ☒ NAD 83 ☐ NAD 27 Source for Latitude/Longitude: ☐ GPS (unit make/model:) (WAAS enabled? ☐ Yes ☐ No) ☒ Land Survey ☐ Topographic Map ☐ Online Mapper:	
		6 Elevation: 1330.20 ft. ☐ Ground Level ☒ TOC Source: ☒ Land Survey ☐ GPS ☐ Topographic Map ☐ Other			

7 WELL WATER TO BE USED AS:

- | | | |
|--|---|---|
| 1. Domestic:
☐ Household
☐ Lawn & Garden
☐ Livestock | 5. ☐ Public Water Supply: well ID | 10. ☐ Oil Field Water Supply: lease |
| 2. ☐ Irrigation | 6. ☐ Dewatering: how many wells? | 11. Test Hole: well ID |
| 3. ☐ Feedlot | 7. ☐ Aquifer Recharge: well ID | ☐ Cased ☐ Uncased ☐ Geotechnical |
| 4. ☐ Industrial | 8. ☒ Monitoring: well ID MW-30 | 12. Geothermal: how many bores? |
| | 9. Environmental Remediation: well ID | a) Closed Loop ☐ Horizontal ☐ Vertical |
| | ☐ Air Sparge ☐ Soil Vapor Extraction | b) Open Loop ☐ Surface Discharge ☐ Inj. of Water |
| | ☐ Recovery ☐ Injection | 13. ☐ Other (specify): |

Was a chemical/bacteriological sample submitted to KDHE? ☐ Yes ☒ No If yes, date sample was submitted:
Water well disinfected? ☐ Yes ☒ No

8 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☐ Glued ☐ Clamped ☐ Welded ☒ Threaded
Casing diameter **1.5** in. to **20** ft., Diameter in. to ft., Diameter in. to ft.
Casing height above land surface **0** in. Weight lbs./ft. Wall thickness or gauge No. **40**

TYPE OF SCREEN OR PERFORATION MATERIAL:

- ☐ Steel ☐ Stainless Steel ☐ Fiberglass ☒ PVC ☐ Other (Specify)
☐ Brass ☐ Galvanized Steel ☐ Concrete tile ☐ None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:

- ☐ Continuous Slot ☒ Mill Slot ☐ Gauze Wrapped ☐ Torch Cut ☐ Drilled Holes ☐ Other (Specify)
☐ Louvered Shutter ☐ Key Punched ☐ Wire Wrapped ☐ Saw Cut ☐ None (Open Hole)

SCREEN-PERFORATED INTERVALS: From **20** ft. to **30** ft., From ft. to ft., From ft. to ft.
GRAVEL PACK INTERVALS: From **18** ft. to **30** ft., From ft. to ft., From ft. to ft.

9 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☒ Other **Bentonite Cement (1-14.5')**
Grout Intervals: From **1** ft. to **14.5** ft., From **14.5** ft. to **18** ft., From ft. to ft.

Nearest source of possible contamination:

- | | | | | |
|---|--|--|---|---|
| ☐ Septic Tank | ☐ Lateral Lines | ☐ Pit Privy | ☐ Livestock Pens | ☐ Insecticide Storage |
| ☐ Sewer Lines | ☐ Cess Pool | ☐ Sewage Lagoon | ☐ Fuel Storage | ☐ Abandoned Water Well |
| ☐ Watertight Sewer Lines | ☐ Seepage Pit | ☐ Feedyard | ☐ Fertilizer Storage | ☐ Oil Well/Gas Well |
| ☐ Other (Specify) | | | | |

Direction from well? Distance from well? ft.

10 FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS
0	0.7	Clay to Silty Sand, blk			
0.7	3	Lean Clay, dk brn to blk			
3	4	No Recovery			
4	25	Lean Clay, dk brn to blk to med brn			
25	26.5	Sandy Clay			
26.5	27.5	Sand, prly grd, brn, fn to med			
27.5	28	No Recovery			
28	30	Sand, prly grd, brn, fn to crs			
30	32	Siltstone, wthrd, lt gry, fn to crs			

Notes:

11 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo-day-year) **01/25/2016** and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. **531** This Water Well Record was completed on (mo-day-year) **03/18/2016** under the business name of **GSI Engineering, LLC**

Send one copy to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.

KS Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-3565.

Visit us at <http://www.kdheks.gov/waterwell/index.html>

KSA 82a-1212

Chal AB



Legend

Well Location

Permeable Reactive Barrier (PRB)

Notes:
1. Site features, property boundaries and well locations are approximate and are not of legal land survey.
2. Basemap source: Golder Associates, drawing titled: "Potentiometric Surface Elevation Map April 2013", dated August, 26, 2013, Figure Number 1, File No. 12384321, Revision 1 (Draft) and modified by Geosyntec in December 2014.
3. Imagery source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AEX, Getmapping, Aerogrid, IGN, IGP, swisstopo, and the GIS User Community.
4. Coordinate system is NAD83, KS South, State Plane Zone 1502, US Survey Foot format

Location	Easting	Northing
IW-12	1654956.71	1710758.11
IW-13	1654939.73	1710760.41
IW-14	1654927.02	1710760.08
IW-15	1654923.79	1710742.45
IW-16	1654904.99	1710740.19
IW-17	1654875.60	1710700.21
IW-18	1654883.78	1710720.26
IW-19	1654864.15	1710720.65
IW-20	1654883.46	1710739.54
IW-21	1654885.60	1710759.52
IW-22	1654906.96	1710759.64
IW-23	1654902.25	1710779.25
IW-24	1654921.84	1710779.29
IW-25	1654941.56	1710781.08
IW-26	1654961.82	1710778.26
MW-28	1654846.54	1710677.86
MW-29	1654564.13	1710579.36
MW-30	1654564.26	1710541.52
MW-31	1654564.64	1710500.84
MW-32	1654565.31	1710451.32
MW-33	1654769.45	1710692.46
MW-34	1654723.11	1710550.71
MW-35	1654932.63	1710755.43

150750150 Feet

Well Installation Locations

USD 259 School Service Center, Wichita, Kansas

Geosyntec[®]
consultants

Guelph

Figure

1

April 2016