

USE TYPEWRITER OR BALL POINT PEN—PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment—Division of Environment (Water well Contractors)  
Topeka, Kansas 66620

Sent to Leonard 4-4-77

1. Location of well:		County <b>Sedgwick</b>	Fraction <b>NE 1/4 NE 1/4 SW 1/4</b>	Section number <b>8</b>	Township number <b>T 26 S R 1 E</b>	Range number <b>1</b>
2. Distance and direction from nearest town or city: <i>1/2 mi. West &amp; 1/2 mi. North of 61st</i> Street address of well location if in city: <i># Broadway - Wichita</i>		3. Owner of well: <b>Park City Improvement Dist. Wichita, Kansas</b>		R.R. or street: City, state, zip code:		
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: <b>Well No. 7 (TH 2-76)</b>		6. Bore hole dia. <u>42</u> in. Completion date <u>3-22-77</u> Well depth <u>49</u> ft.		
5. Type and color of material		From	To	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
<b>Soil</b>		0	3	8. Use: <input type="checkbox"/> Domestic <input checked="" type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
<b>Brown clay</b>		3	13	9. Casing: Material <u>S. St</u> Height: Above <del>surface</del> Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <u>72</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <u>43.77</u> lbs./ft. Dia. <u>12</u> in. to <u>40</u> ft. depth Wall thickness: inches or Dia. <u>   </u> in. to <u>   </u> ft. depth gage No. <u>330</u>		
<b>Med. to coarse sand &amp; gravel</b>		13	45	10. Screen: Manufacturer's name <u>Layne</u> <u>Stainless steel</u> Type <u>W.W.</u> Dia. <u>12"</u> Slot/gauze <u>80</u> Length <u>15'</u> Set between <u>29</u> ft. and <u>44</u> ft. <u>   </u> ft. and <u>   </u> ft. Gravel pack? <u>yes</u> Size range of material <u>1/8x1/2</u>		
<b>Green and gray shale</b>		45	51	11. Static water level: <u>22' 10"</u> below land surface Date <u>3-22-77</u> mo./day/yr.		
				12. Pumping level below land surfaces: <u>24</u> ft. after <u>8</u> hrs. pumping <u>650</u> g.p.m. <u>   </u> ft. after <u>   </u> hrs. pumping <u>   </u> g.p.m. Estimated maximum yield <u>750</u> g.p.m.		
				13. Water sample submitted: <u>   </u> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <u>   </u>		
				14. Well head completion: <input type="checkbox"/> Pitless adapter <u>72</u> inches above grade		
				15. Well grouted? <u>yes</u> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>20</u> ft.		
				16. Nearest source of possible contamination: <u>Flood Channel</u> ft. <u>100</u> Direction <u>East</u> Type <u>Channel</u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
				17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <u>Layne</u> Model number <u>82665</u> HP <u>40</u> Volts <u>460</u> Length of drop pipe <u>35</u> ft. capacity <u>400</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
				(Use a second sheet if needed)		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Layne Western Co. 102</b> Business name <u>Wichita, Kansas</u> License No. <u>   </u> Address <u>   </u> Signed <u>   </u> Date <u>3-30-77</u> Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input checked="" type="checkbox"/> Valley						

26  
10  
NE 1/4 SW 1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5