

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County SEDGWICK	Fraction NE 1/4	Section number 18	Township number T 26 S	Range number R 1E E/W
2. Distance and direction from nearest town or city: Street address of well location if in city: 6001 FAIRFIELD WICHITA KS.			3. Owner of well: JOY JONES R.R. or street: 6001 FAIRFIELD City, state, zip code: WICHITA KANS 67204			
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile		Sketch map: BORED 8" HOLE TO 10' THEN 6" TO 15.5-USED SAND BUCKET TO COMPLETION AT 39'		6. Bore hole dia. 8 in. Completion date 3-15-76 Well depth 39 ft.		
5. Type and color of material		From		To		7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☒ Bored ☐ Reverse rotary
TOP SOIL BLACK		0		2		8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☒ Lawn ☐ Oil field water ☐ Other
SUB SOIL SANDY BROWN		2		4.5		9. Casing: Material RMP Height: 26 Above or below Ground Threaded ☐ Welded ☒ Surface 26 in. RMP ☒ PVC 39 Weight 1.55 lbs./ft. Dia. 5 in. to 39 ft. depth Wall Thickness: inches or Dia. 5 in. to 39 ft. depth gage No. 0200
DIRT, SANDY TAN		4.5		9		10. Screen: Manufacturer's name J+L Type RMP Dia. 5" Slot/auze 0.31 Length 10 Set between 29 ft. and 39 ft. Gravel pack? NO Size range of material
SAND MED. LT. BROWN		9		11		11. Static water level: 15.5 ft. below land surface Date 3-15-76 mo./day/yr.
CLAY GRAY		11		12		12. Pumping level below land surfaces: ft. after hrs. pumping NA g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield 150 g.p.m.
SAND MED. YELLOWISH		12		16		13. Water sample submitted: NO mo./day/yr.
GRAVEL - H2O BROWN		16		21		14. Well head completion: ☐ Pitless adapter 16 inches above grade
SAND MEDIUM - TAN		21		25		15. Well grouted? ☒ With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.
SAND MEDIUM-TO-COARSE		25		30		16. Nearest source of possible contamination: ft. 75 Direction WEST Type CAST-SEWER Well disinfected upon completion? ☐ Yes ☐ No
GRAVEL MEDIUM LIGHT GRAY		30		39		17. Pump: Not installed Manufacturer's name FFW Model number 900A9 HP 9 Volts 230 Length of drop pipe 26 ft. capacity 40 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
HARD PAN - YELLOW		39				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. BEARDEN PUMP & WELL Business name BEARDEN PUMP & WELL License No. 104 Address WICHITA 104 Signed OTIS W. BEARDEN Date 4/8/76 Authorized representative
18. Elevation: 1300 FT. Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley		19. Remarks: (Use a second sheet if needed)				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-3