


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County	Fraction	Section number	Township number	Range number
SEDCRICK		NE NE SE	32	T 26	S R 1 E	E/W
2. Distance and direction from nearest town or city:		3. Owner of well:				
Street address of well location if in city:		R.R. or street:				
WICHITA KANS		WICHITA KANS 67219				
4. Locate with "X" in section below:		Sketch map:				6. Bore hole dia. _____ in. Completion date _____
		DRILLED 9" HOLE TO H ₂ O AT 17' INSTALLED 5" CASING & COMPLETED WITH SAND BUCKETS ROUTED TO 17 FT				Well depth 36 ft. GRADE
5. Type and color of material		From	To	7. Cable tool _____ Rotary _____ Driven _____ Dug _____ Hollow rod _____ Jetted _____ Bored _____ Reverse rotary _____		
TOP SOIL BLACK		0	2	8. Use: _____ Domestic _____ Public supply _____ Industry _____ Irrigation _____ Air conditioning _____ Stock _____ Lawn _____ Oil field water _____ Other _____		
CLAY RED SANDY		2	5	9. Casing: Material RMP Height Above or below _____ Threaded _____ Welded _____ Surface _____ in. RMP _____ PVC _____ Weight 1.55 lbs./ft. Dia. 5 in. to _____ ft. depth _____ ft. Wall Thickness: inches or _____ in. to _____ ft. depth _____ ft. Gauge No. 125		
CLAY GRAY		5	7	10. Screen: Manufacturer's name SUNFLOWER Type RMP Dia. 5 INCH Slot/gauze .031 Length 6 FT. Set between 30 ft. and 36 ft. Gravel pack? NO Size range of material _____		
SAND RED FINE		7	9	11. Static water level: _____ mo./day/yr. _____ ft. below land surface Date 3/21/79		
SAND TAN MEDIUM		9	15	12. Pumping level below land surfaces: _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield 60 g.p.m.		
SAND TAN COARSE		15	18	13. Water sample submitted: _____ mo./day/yr. Yes _____ No _____ Date _____		
CLAY GRAY		18	18.5	14. Well head completion: _____ Pitless adapter _____ 10" _____ inches above grade		
SAND COARSE GRAY		18.5	22	15. Well grouted? YES With: _____ Neat cement _____ Bentonite _____ Concrete _____ Depth: From 3 ft. to 17 ft.		
GRAVEL LARGE BROWN		22	24	16. Nearest source of possible contamination: _____ ft. _____ Direction _____ Type _____ Well disinfected upon completion? _____ Yes _____ No		
SAND COARSE TAN		24	26	17. Pump: _____ Not installed Manufacturer's name FFW Model number 5048 HP 1/2 HP Volts 115 Length of drop pipe 25 ft. capacity 10 g.p.m. Type: _____ Submersible _____ Turbine _____ _____ Jet _____ Reciprocating _____ _____ Centrifugal _____ Other _____		
GRAVEL MEDIUM TAN		26	36	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Business name BEARDEN PUMP & WELL Address 312 MENTON WICHITA Signed _____ Date 4/12/79 Authorized representative		
18. Elevation:		19. Remarks:				
1300 FT		WE BUILT SLAB AROUND WELL - WE HAD PERMISSION TO MAKE WELL 4' FROM PROPERTY LINE PLUGGED OLD SAND POINT AT THIS 29' FROM CONCRETE FLOOR - FILLED WITH SAND TO 3' FROM FLOOR - FILLED TOP 3' WITH CONCRETE - CUT PIPE OFF AT FLOOR LEVEL				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5