

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: FORD SW 1/4 SE 1/4 NE 1/4 32 T 26 S R 25 *XW*

Distance and direction from nearest town or city street address of well if located within city?
 FROM 14TH STREET & BEESON RD. - 3 MILES WEST

2 WATER WELL OWNER: DODGE CITY SAND CO.
 RR#, St. Address, Box #: PO BOX 430
 City, State, ZIP code: DODGE CITY, KS 67801-

Board of Agriculture, Division of Water Resources
 Application Number:

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 177 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 34 ft. below land surface measured on mo/day/yr 05/04/09
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 250 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 15 in. to 177 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: INDUSTRY

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC

CASING JOINTS: GLUED

Blank casing diameter 8 in. to 177 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 30 in., weight 0 lbs/ft. Wall thickness or gauge No. 40

TYPE OF SCREEN OR PERFORATION MATERIAL: PVC

SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 110 ft. to 170 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 20 ft. to 40 ft., From 0 ft. to 0 ft.

From 50 ft. to 177 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE

Grout Intervals: From 0 ft. to 20 ft., From 40 ft. to 50 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: NONE

Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	02 FINE SAND			
3	6	05 CLAY			
6	40	37 FIN-COAR SAN 09 GRAVEL			
40	60	05 CLAY			
60	80	05 CLAY 37 FIN-COAR SAN			
80	100	37 FIN-COAR SAN 06 SMALL GRAVEL 17 CLAY LAYER			
100	120	05 CLAY 37 FIN-COAR SAN			
120	170	37 FIN-COAR SAN 38 SHAL-MED GRA			
170	180	05 CLAY 07 BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/05/09 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 06/08/09 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Judith Creek*

*-DRL
9/4/2009*