


1 LOCATION OF WATER WELL: Fraction NE 1/4 NE 1/4 SW 1/4 Section Number 17 Township Number T 26 S Range Number R 4 EW
 County: Butter

Distance and direction, from nearest town or city street address of well if located within city?

1W 68 Township

2 WATER WELL OWNER: John O Friend
 RR#, St. Address, Box #: 2707 S. Emporia
 City, State, ZIP Code: Wichita, KS 67216
 Board of Agriculture, Division of Water Resources
 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:



4 DEPTH OF COMPLETED WELL: 80 ft. ELEVATION: 70 ft.
 Depth(s) Groundwater Encountered 1. 70 ft. 2. 50 ft. 3. 50 ft.
 WELL'S STATIC WATER LEVEL 50 ft. below land surface measured on mo/day/yr 5/31/95
 Pump test data: Well water was 40 gpm. Well water was 10 ft. after 80 hours pumping 5/31/95 gpm
 Est. Yield 40 gpm. Well water was 10 ft. after 80 hours pumping 5/31/95 gpm
 Bore Hole Diameter: 10 in. to 80 ft., and 10 in. to 80 ft.
 WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well
 ① Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)
 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well
 Was a chemical/bacteriological sample submitted to Department? Yes X No No; If yes, mo/day/yr sample was submitted
 Water Well Disinfected? Yes No

5 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued X Clamped
 ② PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded
 7 Fiberglass Threaded
 Blank casing diameter 5 in. to 80 ft., Dia 5 in. to 80 ft., Dia 5 in. to 80 ft.
 Casing height above land surface 12 in., weight 540 lbs./ft. Wall thickness or gauge No. 540
 TYPE OF SCREEN OR PERFORATION MATERIAL: ⑦ PVC 10 Asbestos-cement
 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)
 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)
 SCREEN OR PERFORATION OPENINGS ARE: 5 Gauzed wrapped 8 Saw cut 11 None (open hole)
 1 Continuous slot ③ Mill slot 6 Wire wrapped 9 Drilled holes
 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)
 SCREEN-PERFORATED INTERVALS: From 60 ft. to 80 ft., From 60 ft. to 80 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 80 ft., From 25 ft. to 80 ft.

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout ③ Bentonite 4 Other
 Grout Intervals: From 3 ft. to 25 ft., From 3 ft. to 25 ft.
 What is the nearest source of possible contamination: 10 Livestock pens 14 Abandoned water well
 1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well
 2 Sewer lines 5 Cess pool ⑧ Sewage lagoon 12 Fertilizer storage 16 Other (specify below)
 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage
 Direction from well? down slope How many feet? 100+

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	earth			
2	10	clay			
10	22	broken rock			
22	40	grey shale			
40	55	shale (dark)			
55	62	red bed			
62	80	lime			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 5/31/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 993 This Water Well Record was completed on (mo/day/yr) 5/31/95 under the business name of Reisner Well Drilling by (signature) Deeey Runyan