

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Sedgwick		SE 1/4 SE 1/4 SW 1/4	21	T 27 S	R 1 EW
Distance and direction from nearest town or city street address of well if located within city? 811 E. Waterman, Wichita, KS.					
2 WATER WELL OWNER:		United Warehouse/Sam Hardage			
RR#, St. Address, Box # :		811 E. Waterman		Board of Agriculture, Division of Water Resources	
City, State, ZIP Code :		Wichita, KS. 67202		Application Number:	
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 20'6" ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. 15' ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 15.82 ft. below land surface measured on mo/day/yr 5-20-96			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter: 8 1/2" in. to 20'6" ft., and in. to ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well			
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)			
		2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes No X If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes No			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued Clamped			
1 Steel 3 RMP (SR)		5 Wrought iron 8 Concrete tile			
2 PVC 4 ABS		6 Asbestos-Cement 9 Other (specify below)			
Blank casing diameter 2.375 in. to 10'3" ft., Dia		7 Fiberglass			
Casing height above land surface 10'3" ft., weight		8 RMP (SR)			
TYPE OF SCREEN OR PERFORATION MATERIAL:		9 ABS			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR)		10 Asbestos-cement			
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS		11 Other (specify)			
SCREEN OR PERFORATION OPENINGS ARE:		12 None used (open hole)			
1 Continuous slot 3 Mill slot		5 Gauzed wrapped 8 Saw cut 11 None (open hole)			
2 Louvered shutter 4 Key punched		6 Wire wrapped 9 Drilled holes			
SCREEN-PERFORATED INTERVALS:		7 Torch cut 10 Other (specify)			
From 20'3" ft. to 10'3" ft., From ft. to ft.					
GRAVEL PACK INTERVALS:					
From 20'6" ft. to 8' ft., From ft. to ft.					
From ft. to ft., From ft. to ft.					
6 GROUT MATERIAL:		4 Other			
1 Neat cement 2 Cement grout 3 Bentonite					
Grout Intervals: From 8' ft. to 4' ft., From 4' ft. to 0' ft., From ft. to ft.					
What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)					
13 Insecticide storage					
Direction from well? North		How many feet? 200'			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	Gravel-roadbase.			
1	3.75	Dk brn clayey gravel, cinders, brick fill w/ ls.rx., gravel, no odor.			
3.75	6	Med-dk brn silty clay, mottled, firm, noodor, oxides.			
6	9.75	Lt brn clayey silt to silty clay, soft, med plasticity, oxides.			
9.75	12.50	Gray brn mottled clayey silt, soft, moist, blk oxide staining, no odor, low plasticity.			
12.50	15	Oxide rust colored fine grained sand, banded, dry-moist, no odor.			
15	20'6"	Fine-coarse sand w/ trace amt of ctz, gravel, pebble size, wet at 15', no odor, well graded.			
F.M. CK'd by Don Taylor					
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 5-20-96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 539. This Water Well Record was completed on (mo/day/yr) 5-23-96 under the business name of JB Environmental Drilling by (signature) James Becker					