

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

Well ID

MW5RR

Original Record Correction Change in Well Use

1 LOCATION OF WATER WELL: County Sedgwick... 2 WELL OWNER: Last Name: Business: KDHE-BER... 3 LOCATE WELL WITH "X" IN SECTION BOX: [Diagram]... 4 DEPTH OF COMPLETED WELL: 19.74 ft... 5 Latitude: 37.70755... 6 Elevation: 1304.05 ft... TOC

7 WELL WATER TO BE USED AS: 1 Domestic: Household, Lawn & Garden... 2 Irrigation... 3 Feedlot... 4 Industrial... 5 Public Water Supply... 6 Dewatering... 7 Aquifer Recharge... 8 Monitoring: well ID MW5RR... 9 Environmental Remediation... 10 Oil Field Water Supply... 11 Test Hole... 12 Geothermal...

Was a chemical/bacteriological sample submitted to KDHE? Yes No... Water well disinfected? Yes No

8 TYPE OF CASING USED: Steel PVC Other... CASING JOINTS: Glued Clamped Welded Threaded... TYPE OF SCREEN OR PERFORATION MATERIAL: Steel Stainless Steel Fiberglass PVC... SCREEN OR PERFORATION OPENINGS ARE: Continuous Slot Mill Slot Gauze Wrapped Torch Cut Drilled Holes... SCREEN-PERFORATED INTERVALS: From 9.74 ft. to 19.74 ft... GRAVEL PACK INTERVALS: From 8 ft. to 20.5 ft...

9 GROUT MATERIAL: Neat cement Cement grout Bentonite Other Concrete: 0-0.5'... Grout intervals: From 0.5 ft. to 8 ft...

Nearest source of possible contamination: Septic Tank Lateral Lines Pit Privy Livestock Pens Insecticide Storage... Sewer Lines Cess Pool Sewage Lagoon Fuel Storage Abandoned Water Well... Watertight Sewer Lines Seepage Pit Feedyard Fertilizer Storage Oil Well / Gas Well... Other (Specify)...

10 FROM TO LITHOLOGIC LOG FROM TO LITHO. LOG (cont.) or PLUGGING INTERVALS... 0 0.8 Gravel... 0.8 4 Medium brown silty clay... 4 5 Tan clay... 5 7 Tan silty clay... 7 9 Dark tan silty sand... 9 18 Fine light tan sand... 18 20.5 Fine gray sand... Notes: KDHE ID: Klepper Korner Store; U2-087-01277

11 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed, reconstructed, or plugged under my jurisdiction and was completed on (mo-day-year) 2/2/16... License No 757... Signature [Signature]

TRITERRA LAND SERVICES

P.O. Box 546
Clearwater, Kansas 67026
Cell (316) 648-3617
Fax (620) 584-4371
Email: triterrals@yahoo.com

SURVEYING OF REPLACEMENT AND ADDITIONAL MONITORING WELL
KLEPPER KORNER STORE
WICHITA, KANSAS

The site is located in the Section 9, Township 27 South, Range 1 East of the Sixth Principal Meridian, Sedgwick County, Kansas. The Southeast corner of Section 9 was assigned coordinates of 00.00 North and 00.00 West.

The top of casing of MW-2 was used for vertical control. A new control point was established as a chiseled 'X' on the SW corner of the base of the signal light on the southwest corner of the intersection.

The Latitude and Longitude were recorded from a GPS unit. The site is located on the 7.5' quad map titled "Wichita East".

ID	NORTH	WEST	LATITUDE	LONGITUDE	ELEVATION
SE CORNER 9-27S-1E	00.00	00.00			
CP	-52.91	3037.18	37.70792	97.32784	1303.91
MW-5RR(Sec 16) NW NE NE NW	-180.16	3033.15	37.70755	97.32788	RIM 1304.29 TOC 1304.05
MW-12(Sec 16) NW NE NE NW	-95.23	3200.84	37.70780	97.32841	RIM 1305.68 TOC 1305.46

