

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
County: Sedgwick		NE 1/4 SW 1/4 SW 1/4		21		T 27 S		R 1 E/W	
Distance and direction from nearest town or city street address of well if located within city?									EAST
Located behind address 401 South Emporia, Wichita, Kansas									HWST Job No.: 74-40/4013.01
2 WATER WELL OWNER:		TAP Partnership							
RR#, St. Address, Box # :		150 N. Main, Suite 501							
City, State, ZIP Code :		Wichita, Kansas 67202							
Board of Agriculture, Division of Water Resources		Application Number:							
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 22.0 ft. ELEVATION: n/a.							
		Depth(s) Groundwater Encountered 1. 14.0 ft. 2. ft. 3. ft.							
		WELL'S STATIC WATER LEVEL 14.73 ft. below land surface measured on mo/day/yr 5/10/90							
		Pump test data: Well water was ft. after hours pumping gpm							
		Est. Yield 10 gpm: Well water was ft. after hours pumping gpm							
		Bore Hole Diameter 6.0 in. to 22.0 ft., and in. to ft.							
5 TYPE OF BLANK CASING USED:		5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped							
1 Steel 3 RMP (SR)		6 Asbestos-Cement 9 Other (specify below) Welded							
1/2 PVC 4 ABS		7 Fiberglass Threaded X							
Blank casing diameter 2.0 in. to 12.0 ft., Dia in. to ft., Dia in. to ft.		Casing height above land surface flush in., weight lbs./ft. Wall thickness or gauge No. Sch 40							
TYPE OF SCREEN OR PERFORATION MATERIAL:		X PVC 10 Asbestos-cement							
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)		2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)							
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)							
1 Continuous slot X Mill slot 6 Wire wrapped 9 Drilled holes		2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)							
SCREEN-PERFORATED INTERVALS:		From 22.0 ft. to 12.0 ft., From ft. to ft.							
GRAVEL PACK INTERVALS:		From 22.0 ft. to 12.0 natural ft., From 12.0 ft. to 10.0 sand ft.							
6 GROUT MATERIAL:		1 Neat cement 2 Cement grout X Bentonite 4 Other							
Grout Intervals: From 8.0 ft. to grade ft., From ft. to ft., From ft. to ft.		What is the nearest source of possible contamination:							
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well		2 Sewer lines 5 Cess pool 8 Sewage lagoon XI Fuel storage 15 Oil well/Gas well							
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)		13 Insecticide storage							
Direction from well? North		How many feet? Approx. 50.0'							
FROM TO LITHOLOGIC LOG FROM TO PLUGGING INTERVALS									
0.0 0.5 Concrete:									
0.5 1.0 Fill: Sand:									
1.0 5.0 Sand: light brown; less than 5% fines; fine to medium sand.									
5.0 11.0 Sand: light reddish-brown; less than 5% fines; medium to coarse sand.									
11.0 16.0 Sand: light brown; less than 10% fines; less than 5% gravel; medium to coarse sand.									
16.0 22.0 Sand: light grayish-brown; less than 15% fines; less than 10% gravel; fine to medium sand.									
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (X) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) May 9, 1990 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 471 This Water Well Record was completed on (mo/day/yr) 5/17/90 under the business name of HWS Technologies Inc. by (signature) [Signature]									
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-7320. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.									