

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
County: Sedgwick		NW 1/4 NW 1/4 SW 1/4		16		T 27 S		R 1 EW	
Distance and direction from nearest town or city street address of well if located within city?									
803 North Broadway, Wichita, Kansas									
2 WATER WELL OWNER:		Town & Country Markets				01948036 MW-4			
RR#, St. Address, Box # :		P.O. Box 17087				Board of Agriculture, Division of Water Resources			
City, State, ZIP Code :		Wichita, Kansas 67217				Application Number:			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL		21.5		ft. ELEVATION:		1301.45	
1 Mile W NW NE SW SE X S		Depth(s) Groundwater Encountered		1. 16.5		ft. 2.		ft. 3.	
		WELL'S STATIC WATER LEVEL		14.95		ft. below land surface measured on mo/day/yr		10/27/94	
		Pump test data:		Well water was		ft. after		hours pumping	
		Est. Yield		N/A		gpm: Well water was		ft. after	
		Bore Hole Diameter		8.25		in. to		21.5	
WELL WATER TO BE USED AS:		5 Public water supply		8 Air conditioning		11 Injection well			
		1 Domestic		3 Feedlot		6 Oil field water supply		9 Dewatering	
		2 Irrigation		4 Industrial		7 Lawn and garden only		10 Monitoring well	
Was a chemical/bacteriological sample submitted to Department? Yes		No		X		If yes, mo/day/yr sample was submitted			
Water Well Disinfected? Yes		No		X					
5 TYPE OF BLANK CASING USED:		3 Wrought iron		8 Concrete tile		CASING JOINTS: Glued		Clamped	
1 Steel		3 RMP (SR)		6 Asbestos-Cement		9 Other (specify below)		Welded	
2 PVC		4 ABS		7 Fiberglass				Threaded	
Blank casing diameter		2		in. to		11.5		ft., Dia	
Casing height above land surface		-3		in., weight		lbs./ft. Wall thickness or gauge No.		Schedule 40	
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC		10 Asbestos-cement					
1 Steel		3 Stainless steel		5 Fiberglass		8 RMP (SR)		11 Other (specify)	
2 Brass		4 Galvanized steel		6 Concrete tile		9 ABS		12 None used (open hole)	
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped		8 Saw cut		11 None (open hole)			
1 Continuous slot		3 Mill slot		6 Wire wrapped		9 Drilled holes			
2 Louvered shutter		4 Key punched		7 Torch cut		10 Other (specify)			
SCREEN-PERFORATED INTERVALS:		From		11.5		ft. to		21.5	
GRAVEL PACK INTERVALS:		From		9.5		ft. to		21.5	
6 GROUT MATERIAL:		1 Neat cement		2 Cement grout		3 Bentonite		4 Other	
Grout Intervals:		From		0		ft. to		7.5	
What is the nearest source of possible contamination:		10 Livestock pens		14 Abandoned water well					
1 Septic tank		4 Lateral lines		7 Pit privy		11 Fuel storage		15 Oil well/Gas well	
2 Sewer lines		5 Cess pool		8 Sewage lagoon		12 Fertilizer storage		16 Other (specify below)	
3 Watertight sewer lines		6 Seepage pit		9 Feedyard		13 Insecticide storage		UST	
Direction from well?		How many feet?							
FROM		TO		LITHOLOGIC LOG		FROM		TO	
0.0		0.3		Grass					
0.3		4.0		Brown, Sandy Lean Clay					
4.0		9.0		Brown, Sandy Fat Clay					
9.0		13.5		Brown, Sandy Lean Clay					
13.5		21.5		Brown, Fine to Coarse Sand					
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was 1 constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 10/21/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 416 This Water Well Record was completed on (mo/day/yr) 11-18-94 under the business name of Terracon Consultants, Inc. by (signature) Steve Fischer									
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.									