

WELL RECORD

Well No. WSW-2 Farm Barker Producer Belleair Oil Corp.
 Location _____ Sec. 4 Twp. 27-S Rg. 18-E
 Elevation _____ State Kansas County Neosho
 Kind (Oil, Gas, Water, Dry Hole) Water Contractor Mayfield & Sutcliffe
 Producing formation _____ Top _____ Bottom _____
 Shot with _____ qts. _____ from _____ to _____
 Packer Set at _____ Kind _____ Size _____
 Liner _____ from _____ to _____ Perforated from _____ to _____

LOG

Thick-ness	Strata	Depth	Thick-ness	Strata	Depth
3	Soil	3	3	Lime	523
18	Clay	21	28	Shale	551
3	Gravel	24	16	Lime	567
2	Shale	26	5	Shale	572
8	Lime	34	5	Lime	577
2	Shale	36	55	Shale	632
4	Lime	40	36	Shale	668
18	Shale	58	2	Lime	670
4	Lime	62	63	Shale	733
2	Shale	64	28	Sandy Shale	761
61	Lime	125	51	Shale	812
3	Shale	128	13	Sandy Shale	825
10	Lime	138	Cored from 825' to 850'		
2	Shale	140	64	Sand	914
18	Lime	158	10	Sandy shale	924
4	Shale	162	7	Shale	931
42	Lime	204	39	Sand	970
6	Shale	210	28	Black shale	998
115	Shale	325	2	Chat	1000
10	Lime shells	335	5	Lime	1005
30	Shale	365	11	Lime	1016
15	Lime	380	2	Slate	1018
5	Shale	395	204	Lime	1222
14	Lime	399	29	Shale	1251
7	Shale	406	24	Lime	1275
6	Lime shells	412			
16	Shale	428			
24	Sand	452			
40	Shale	492			
25	Lime	517			

Total Depth 1275'
 Open Hole _____
 Casing 12 1/2" at 26'
 Casing 10" at 210'
 Casing 8 1/4" at 632'
 Cement 6-5/8" 1005'
 Tubing _____
 Rods _____
 Additional Information _____
Little water at 36'
5 bailers per hour of water @ 64'
set 10" pipe at 210'
Water at 520'
S.L.M. at 551 feet
20' water at 572'
set 8" at 632' - SLM
SLM at 765.5
Water at 761'
S.L.M. at 825'
SLM at 1005' - set 6-5/8" casing
& cemented by Halliburton
Water at 1074 - - 400' in hole
Water 363' from top of hole

3 Black Slate 520
 Date Completed January 13, 1953 O. K.
 Date started December 31, 1952

Superintendent _____

