

[1] LOCATION OF WATER WELL: County: <u>Sedgwick</u>		Fraction <u>NW 1/4 SW 1/4 SE 1/4</u>	Section Number <u>13</u>	Township Number T <u>27</u> S	Range Number R <u>2</u> E <u>MX</u>
Distance and direction from nearest town or city street address of well if located within city? <u>15202 Stratford Row, Wichita, KS 67230</u>					
[2] WATER WELL OWNER:	Mark Beal				
RR#, St. Address, Box # :	<u>15202 Stratford Row</u>				
City, State, ZIP Code :	<u>Wichita, KS 67230</u>				
Board of Agriculture, Division of Water Resources Application Number:					
[3] LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	[4] DEPTH OF COMPLETED WELL... <u>92</u> ft. ELEVATION:				
N E S W	Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.				
	WELL'S STATIC WATER LEVEL ... <u>28</u> ft. below land surface measured on mo/day/yr ... <u>8/29/98</u>				
	Pump test data: Well water was ft. after hours pumping gpm				
	Est. Yield gpm: Well water was ft. after hours pumping gpm				
	Bore Hole Diameter.... <u>9</u> in. to ... <u>92</u> ft., and..... in. to				
	WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well				
	1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)				
	2 Irrigation 4 Industrial [7] Lawn and garden only 10 Monitoring well				
Was a chemical/bacteriological sample submitted to Department? Yes.....No..... <u>X</u>; If yes, mo/day/yr sample was submitted					
Water Well Disinfected? Yes <u>X</u> No					
[5] TYPE OF BLANK CASING USED:	CASING JOINTS: Glued .. <u>X</u> .. Clamped				
1 Steel	3 RMP (SR)	5 Wrought iron	8 Concrete tile	Welded	
[2] PVC	4 ABS	6 Asbestos-Cement	9 Other (specify below)	Threaded.....	
Blank casing diameter ... <u>5</u> in. to ... <u>52</u> ft., Dia	in. toft., Dia in. toft.				
Casing height above land surface ... <u>13</u> in., weight	lbs./ft. Wall thickness or gauge No. <u>SDR26</u>				
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel	3 Stainless steel	5 Fiberglass	[7] PVC	10 Asbestos-cement	
2 Brass	4 Galvanized steel	6 Concrete tile	8 RMP (SR)	11 Other (specify)	
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot	3 Mill slot	5 Gauzed wrapped	[8] Saw cut	11 None (open hole)	
2 Louvered shutter	4 Key punched	6 Wire wrapped	9 Drilled holes		
SCREEN-PERFORATED INTERVALS: From ... <u>52</u> ft. to ... <u>92</u> ft., Fromft. toft.					
GRAVEL PACK INTERVALS: From ... <u>20</u> ft. to ... <u>92</u> ft., Fromft. toft.					
FROMft. toft., FROMft. toft.					
[6] GROUT MATERIAL:	1 Neat cement	2 Cement grout	[3] Bentonite	4 Other	
Grout Intervals: From ... <u>4</u> ft. to ... <u>20</u> ft., Fromft. toft., Fromft. toft.					
What is the nearest source of possible contamination:					
1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well	
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well	
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)	
Direction from well?					
How many feet?					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	28	Clay			
28	46	Shale			
46	48	Lime			
48	78	Shale w/ lime stks.			
78	92	Cherty lime			
[7] CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was [1] constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) ... <u>8/29/98</u> ... and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. ... <u>171</u> ... This Water Well Record was completed on (mo/day/yr) ... <u>8/31/98</u> ... under the business name of <u>G & S Drilling, Inc.</u> by (signature) <u>Timothy E. BRANDT</u>					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answer. Send one to WATER WELL OWNER and retain one for your records.					