

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: <u>SEDGWICK</u>		<u>SW 1/4 NW 1/4 NW 1/4</u>	<u>10</u>	<u>T 27 S</u>	<u>R 2 EW</u>
Distance and direction from nearest town or city street address of well if located within city? <u>NE OF 13th & GREENWICH RD WICHITA KS</u> <u>MW SAL 31-1</u>					
2 WATER WELL OWNER:		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box # <u>9709 E CENTRAL</u>		Application Number:			
City, State, ZIP Code <u>WICHITA KS 67207</u>					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: <u>55</u> ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL ft. below land surface measured on mo/day/yr			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter <u>7 1/4</u> in. to <u>55</u> ft., and in. to ft.			
		WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well			
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)			
		2 Irrigation 4 Industrial 7 Lawn and garden only ☒ Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes No ; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes No			
5 TYPE OF BLANK CASING USED:					
1 Steel		3 RMP (SR)		5 Wrought iron	
☒ PVC		4 ABS		8 Concrete tile	
Blank casing diameter <u>2</u> in. to <u>35</u> ft., Dia in. to ft., Dia in. to ft.		6 Asbestos-Cement		CASING JOINTS: Glued Clamped	
Casing height above land surface <u>0</u> in., weight <u>SCHED 40</u> lbs./ft. Wall thickness or gauge No.		7 Fiberglass		9 Other (specify below) Welded	
TYPE OF SCREEN OR PERFORATION MATERIAL:		☒ PVC		10 Asbestos-cement	
1 Steel		3 Stainless steel		11 Other (specify)	
2 Brass		4 Galvanized steel		12 None used (open hole)	
5 Fiberglass		8 RMP (SR)			
6 Concrete tile		9 ABS			
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped		8 Saw cut	
1 Continuous slot		☒ Mill slot <u>9/10</u>		11 None (open hole)	
2 Louvered shutter		6 Wire wrapped		9 Drilled holes	
4 Key punched		7 Torch cut		10 Other (specify)	
SCREEN-PERFORATED INTERVALS: From <u>55</u> ft. to <u>35</u> ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From <u>55</u> ft. to <u>31</u> ft., From ft. to ft.					
		From ft. to ft., From ft. to ft.			
		From ft. to ft., From ft. to ft.			
		From ft. to ft., From ft. to ft.			
6 GROUT MATERIAL: 1 Neat cement ☒ Cement grout ☒ Bentonite 4 Other					
Grout intervals: From <u>27</u> ft. to <u>26</u> ft., From <u>31</u> ft. to <u>27</u> ft., From ft. to ft.					
What is the nearest source of possible contamination:					
1 Septic tank		4 Lateral lines		7 Pit privy	
2 Sewer lines		5 Cess pool		8 Sewage lagoon	
☒ Watertight sewer lines		6 Seepage pit		9 Feedyard	
10 Livestock pens		14 Abandoned water well		11 Fuel storage	
11 Fuel storage		15 Oil well/Gas well		12 Fertilizer storage	
12 Fertilizer storage		16 Other (specify below)		13 Insecticide storage	
Direction from well? <u>West</u>		How many feet? <u>1500'</u>			
LITHOLOGIC LOG					
FROM	TO		FROM	TO	PLUGGING INTERVALS
0	4	Silty loam Brn	44	45	Very Silty clay
4	8	Brn stiff silty clay w/Caliche	45	52	Broken shale & silt
8	13	Clayey silt light olive Brn	52	55	Silty shale traces of gypsum
13	15	Oliver silty clay			
15	20	Clayey silt, light olive			
20	21	Weathered limestone			
21	24	Silty clay olive yellow			
24	30	Silty clay olive w/Brn limestone			
30	34	Silt pale olive			
34	35	Silty clay olive			
35	37	Silt w/ weathered shale Brn olive			
37	39	Silt & limestone pale Brn			
39	41	Silty clay olive Brn			
41	44	Silt & shale pale olive			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>11-28-99</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>575</u> This Water Well Record was completed on (mo/day/yr) <u>3-14-00</u> under the business name of <u>FUNKIE DRILLING SERVICE INC</u> by (signature) <u>[Signature]</u>					