

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: <u>SEDGWICK</u>		<u>SW 1/4 NW 1/4 NE 1/4</u>	<u>15</u>	<u>T 27 S</u>	<u>R 2 E</u>
Distance and direction from nearest town or city street address of well if located within city? <u>1/4 mile west of 127th east 1/2 mile N of central MNW 11-N</u>					
2 WATER WELL OWNER:		Just East of R-96			
RR#, St. Address, Box #:		Board of Agriculture, Division of Water Resources			
City, State, ZIP Code:		Application Number:			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: <u>60</u> ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. _____ ft. 2. _____ ft. 3. _____ ft.			
		WELL'S STATIC WATER LEVEL _____ ft. below land surface measured on mo/day/yr			
		Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm			
		Est. Yield _____ gpm: Well water was _____ ft. after _____ hours pumping _____ gpm			
		Bore Hole Diameter: <u>7 1/4</u> in. to <u>60</u> ft., and _____ in. to _____ ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only ☒ Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes _____ No ☒ If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes _____ No ☒			
5 TYPE OF BLANK CASING USED:					
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued _____ Clamped _____ ☒ PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded _____ 7 Fiberglass Threaded ☒					
Blank casing diameter <u>2</u> in. to <u>44.5</u> ft., Dia _____ in. to _____ ft., Dia _____ in. to _____ ft.					
Casing height above land surface <u>0</u> in., weight <u>SCHED 40</u> lbs./ft. Wall thickness or gauge No. _____					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify) _____ 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot ☒ Mill slot <u>0.10</u> 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify) _____					
SCREEN-PERFORATED INTERVALS: From <u>60</u> ft. to <u>44.5</u> ft., From _____ ft. to _____ ft.					
GRAVEL PACK INTERVALS: From <u>60</u> ft. to <u>40</u> ft., From _____ ft. to _____ ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout ☒ Bentonite 4 Other _____					
Grout Intervals: From _____ ft. to _____ ft., From <u>40</u> ft. to <u>1.3</u> ft., From _____ ft. to _____ ft.					
What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well ☒ Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) _____ 13 Insecticide storage					
Direction from well? <u>East</u> How many feet? <u>570'</u>					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	Topsoil Dark Brn Silty clay	38.5	42.5	limey shale light gray
1	15	Silty clay gray green	42.5	43	Shale gray green weathered
15	15.5	limestone	43	50	limey shale pinkish gray hard
15.5	18	Silt & weath erid Gypsum	50	51.5	Shale gray green
18	18.25	limestone gray	51.5	55	limey shale light gray
18.25	19	gray green silty clay	55	55	Clayey silt olive green
19	21	Silty shale pinkish tan	55	56	Shale blk
21	21.5	Clayey silt gray green	56	58	limey shale pinkish gray
21.5	25	Silty clay gray green	58	58.5	limestone gray weathered
25	27.5	Silty clay 11 12 W Gyp	58.5	60	Shale pinkish gray to Black weathered very hard
27.5	28	limestone			
28	31	Silty clay olive green			
31	35.5	olive green to Maroon silty clay			
35.5	36	limestone gray crystalline			
36	38.5	Silty clay gray green			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>1-21-00</u> and this record is true to the best of my knowledge and belief. Kansas					
Water Well Contractor's License No. <u>575</u> This Water Well Record was completed on (mo/day/yr) <u>3-24-00</u>					
under the business name of <u>FUNKER</u> by (signature) <u>Al L Kunt</u>					