

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: SEDGWICK		SW 1/4 NW 1/4 SW 1/4	10	T 27 S	R 2 EW
Distance and direction from nearest town or city street address of well if located within city? MW# SAL 16					
1/2 MILE NORTH OF 13th ST. OFF OF GREENWICH RD					
2 WATER WELL OWNER: RAYTHEON AIRCRAFT CO		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box #: 9709 EAST CENTRAL		Application Number:			
City, State, ZIP Code: WICHITA, KS 67206					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 37.5 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL ft. below land surface measured on mo/day/yr			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter: 7 1/4 in. to 37.5 ft. and in. to ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes.....No.....; If yes, mo/day/yr sample was submitted			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued Clamped			
1 Steel 3 RMP (SR)		5 Wrought iron 8 Concrete tile			
2 PVC 4 ABS		6 Asbestos-Cement 9 Other (specify below) Welded			
		7 Fiberglass X Threaded			
Blank casing diameter: 2 in. to 27.5 ft. Dia. in. to ft. Dia. in. to ft.					
Casing height above land surface: 0 in., weight: sched 40 lbs./ft. Wall thickness or gauge No.					
TYPE OF SCREEN OR PERFORATION MATERIAL:		X7 PVC 10 Asbestos-cement			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)					
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)			
1 Continuous slot X3 Mill slot 0.10 6 Wire wrapped 9 Drilled holes					
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From 37.5 ft. to 27.5 ft. From ft. to ft.					
GRAVEL PACK INTERVALS: From 37.5 ft. to 24 ft. From ft. to ft.					
6 GROUT MATERIAL: 1 Neat cement X2 Cement grout X3 Bentonite 4 Other					
Grout intervals: From 21 ft. to 0.03 ft. From 24 ft. to 21 ft. From ft. to ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)					
X3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage					
Direction from well? west		How many feet? 1200			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	4	DARK BRN SILTY CLAY			
4	7	SILTY LIGHT OLIVE BRN CLAY			
7	14	SILTY LIGHT OLIVE BRN CLAY			
14	18	LIGHT OLIVE BRN SILTY CLAY			
18	19	SILTY LIMESTONE			
19	23	PALE YELLOW CALCAREOUS SILT			
23	26	OLIVE BRN CLAYEY SILT			
26	35	MEDIUM STIFF PLASTIC LIGHT OLIVE BRN SILTY CLAY			
35	37	BROKEN SHALE LIGHT OLIVE BRN			
37	37.5	GYPSUM WHITE HARD			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) Xconstructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 5-27-98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 575 This Water Well Record was completed on (mo/day/yr) 7-12-98 under the business name of KURTZ ENVIRONMENTAL SERVICE by (signature)					