

GMW-8

Form WWC-5

Division of Water Resources App. No.

1 LOCATION OF WATER WELL: County: Sedgwick		Fraction NW ¼ NW ¼ N ½ NW ¼		Section Number 29	Township No. T 27 S	Range Number R 2 ☒ E ☐ W
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ . Amoco #9598 8001 E. Kellogg Ave., Wichita, KS				Global Positioning System (GPS) information: Latitude: 37.6795 (in decimal degrees) Longitude: 97.2449 (in decimal degrees) Elevation: _____ Datum: ☐ WGS 84, ☒ NAD 83, ☐ NAD 27 Collection Method: ☒ GPS unit (Make/Model: Garmin 60) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☒ 3-5 m, ☐ 5-15 m, ☐ >15 m		
2 WATER WELL OWNER: RR#, Street Address, Box #: 501 Westlake Park Blvd City, State, ZIP Code : Houston, TX 77079						

3 LOCATE WELL WITH AN "X" IN SECTION BOX:

N

X -- NW -- -- SW -- 	-- NE -- -- SE --
------------------------------------	-------------------------------

S

W E

|-----1 mile-----|

4 DEPTH OF COMPLETED WELL 28 ft.

Depth(s) Groundwater Encountered (1) 28 ft. (2) — ft. (3) — ft.

WELL'S STATIC WATER LEVEL 1.5 ft. below land surface measured on mo/day/yr.

Pump test data: Well water was 28 ft. after — hours pumping — gpm

EST. YIELD — gpm. Well water was 28 ft. after — hours pumping — gpm

Bore Hole Diameter 8 in. to 28 ft., and — in. to — ft.

WELL WATER TO BE USED AS:

☐ Public water supply	☐ Geothermal	☐ Injection well
☐ Domestic	☐ Feedlot	☐ Oil field water supply
☐ Dewatering	☐ Other (Specify below)	
☐ Irrigation	☐ Industrial	☐ Domestic-lawn & garden
☒ Monitoring well		

Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No

If yes, mo/day/yr sample was submitted —

Water well disinfected? ☐ Yes ☒ No

5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other

CASING JOINTS: ☐ Glued ☐ Clamped ☐ Welded ☒ Threaded

Casing diameter 2..... in. to 13..... ft., Diameter in. to ft., Diameter in. to ft.

Casing height above land surface. Flush..... in., Weight lbs./ft., Wall thickness or gauge No. Sch. 40.....

TYPE OF SCREEN OR PERFORATION MATERIAL:

☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify)

☐ Brass ☐ Galvanized Steel ☐ None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:

☐ Continuous slot ☒ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole)

☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☐ Saw cut ☐ Other (specify)

SCREEN-PERFORATED INTERVALS: From 2.8..... ft. to 13..... ft., From ft. to ft.

From ft. to ft., From ft. to ft.

GRAVEL PACK INTERVALS: From 2.8..... ft. to 11..... ft., From ft. to ft.

From ft. to ft., From ft. to ft.

6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other

Grout Intervals: From ft. to ft., From ft. to ft., From ft. to ft.

What is the nearest source of possible contamination:

☐ Septic tank	☐ Lateral lines	☐ Pit privy	☐ Livestock pens	☐ Insecticide storage	☒ Other (specify below)
☐ Sewer lines	☐ Cesspool	☐ Sewage lagoon	☐ Fuel storage	☐ Abandoned water well	
☐ Watertight sewer lines	☐ Seepage pit	☐ Feedyard	☐ Fertilizer storage	☐ Oil well/gas well	Gas Station

Direction from well Distance from well

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS
0	1	Asphalt/gravel			
1	10	Clay, brown			
10	15	Silty clay w/ trace sand			
15	17.5	Sand w/ trace silt			
17.5	18.6	clay			
18.6	20	Silty clay			
20	26.3	clay w/ sand			
26.3	26.4	sand lens			
26.4	28	clay w/ sand			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 1/25/11 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 710 This Water Well Record was completed on (mo/day/year) 2/4/2011 under the business name of Below Ground Surface, Inc. by (signature) [Signature]

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St, Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at <http://www.kdheks.gov/waterwell/index.html>.