

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: FORD	Fraction SE 1/4 NE 1/4 SW 1/4	Section Number 7	Township Number T 27 S	Range Number R 24 E W																																																						
Distance and direction from nearest town or city street address of well if located within city? FROM DODGE CITY, KS - 1 MILE SOUTH																																																										
2 WATER WELL OWNER: RR#, St. Address, Box # : 1808 BURR PARKWAY City, State, ZIP code : DODGE CITY, KS 67801-		Board of Agriculture, Division of Water Resources Application Number: 10866																																																								
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 172 ELEVATION: 0 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.																																																								
<table border="1" style="width:100%; border-collapse: collapse; text-align: center;"> <tr> <td style="width:5%;">1</td> <td style="width:5%;">2</td> <td style="width:5%;">3</td> <td style="width:5%;">4</td> <td style="width:5%;">5</td> <td style="width:5%;">6</td> <td style="width:5%;">7</td> <td style="width:5%;">8</td> <td style="width:5%;">9</td> <td style="width:5%;">10</td> </tr> <tr> <td colspan="2">NW</td> <td colspan="2"></td> <td colspan="2">NE</td> <td colspan="4"></td> </tr> <tr> <td colspan="2">Mile</td> <td colspan="2">W</td> <td colspan="2">E</td> <td colspan="4"></td> </tr> <tr> <td colspan="2">SW</td> <td colspan="2">X</td> <td colspan="2">SE</td> <td colspan="4"></td> </tr> </table>		1	2	3	4	5	6	7	8	9	10	NW				NE						Mile		W		E						SW		X		SE						WELL'S STATIC WATER LEVEL 79 ft. below land surface measured on mo/day/yr 05/20/97 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm																
		1	2	3	4	5	6	7	8	9	10																																															
		NW				NE																																																				
		Mile		W		E																																																				
SW		X		SE																																																						
Estimated Yield 650 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm																																																										
Bore Hole Diameter 26 in. to 172 ft., and in. to 0 ft.																																																										
WELL WATER TO BE USED AS: IRRIGATION																																																										
Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes																																																										
5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED Blank casing diameter 16 in. to 172 ft., Dia in. to 0 ft., Dia in. to 0 ft. Casing height above land surface 12 in., weight 0 lbs/ft. Wall thickness or gauge No. 40 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC SCREEN OR PERFORATION OPENINGS ARE: MILL SLOT																																																										
SCREEN PERFORATED INTERVALS: From 112 ft. to 172 ft., From 0 ft. to 0 ft. GRAVEL PACK INTERVALS: From 0 ft. to 0 ft., From 0 ft. to 0 ft. From 20 ft. to 172 ft., From 0 ft. to 0 ft. From 0 ft. to 0 ft., From 0 ft. to 0 ft.																																																										
6 GROUT MATERIAL BENTONITE Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft. What is the nearest source of possible contamination: ABANDONED WELL Direction from well? NORTH How many feet? 130																																																										
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th style="width:10%;">FROM</th> <th style="width:10%;">TO</th> <th style="width:40%;">LITHOLOGIC LOG</th> <th style="width:10%;">FROM</th> <th style="width:10%;">TO</th> <th style="width:20%;">PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>20</td> <td>TOPSOIL CLAY</td> <td></td> <td></td> <td></td> </tr> <tr> <td>20</td> <td>40</td> <td>CLAY FINE - MED SAND</td> <td></td> <td></td> <td></td> </tr> <tr> <td>40</td> <td>60</td> <td>MED-COARSE SAND</td> <td></td> <td></td> <td></td> </tr> <tr> <td>60</td> <td>100</td> <td>MED-COARSE SAND SMALL GRAVEL</td> <td></td> <td></td> <td></td> </tr> <tr> <td>100</td> <td>120</td> <td>MED-COARSE SAND SMALL GRAVEL CLAY LAYERS</td> <td></td> <td></td> <td></td> </tr> <tr> <td>120</td> <td>140</td> <td>FINE - MED SAND SMALL GRAVEL CLAY LAYERS</td> <td></td> <td></td> <td></td> </tr> <tr> <td>140</td> <td>163</td> <td>FINE SAND COARSE SAND SMALL GRAVEL</td> <td></td> <td></td> <td></td> </tr> <tr> <td>163</td> <td>172</td> <td>CLAY THIN ROCK LAYER BLUE SHALE</td> <td></td> <td></td> <td></td> </tr> </tbody> </table>					FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS	0	20	TOPSOIL CLAY				20	40	CLAY FINE - MED SAND				40	60	MED-COARSE SAND				60	100	MED-COARSE SAND SMALL GRAVEL				100	120	MED-COARSE SAND SMALL GRAVEL CLAY LAYERS				120	140	FINE - MED SAND SMALL GRAVEL CLAY LAYERS				140	163	FINE SAND COARSE SAND SMALL GRAVEL				163	172	CLAY THIN ROCK LAYER BLUE SHALE			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS																																																					
0	20	TOPSOIL CLAY																																																								
20	40	CLAY FINE - MED SAND																																																								
40	60	MED-COARSE SAND																																																								
60	100	MED-COARSE SAND SMALL GRAVEL																																																								
100	120	MED-COARSE SAND SMALL GRAVEL CLAY LAYERS																																																								
120	140	FINE - MED SAND SMALL GRAVEL CLAY LAYERS																																																								
140	163	FINE SAND COARSE SAND SMALL GRAVEL																																																								
163	172	CLAY THIN ROCK LAYER BLUE SHALE																																																								
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/23/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 06/23/97 under the business name of JOE'S WELL SERVICE, INC. by (signature) <i>Joseid Cruz</i>																																																										