

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Bourbon	Fraction SW 1/4 SW 1/4 SE 1/4	Section number 7	Township number T 27 S	Range number R 25 E
2. Distance and direction from nearest town or city: 8 mi. S. 1/4 W.			3. Owner of well: HARRY DENTON			
Street address of well location if in city: 1/4 FT. SCOTT. 1/4 N			R.R. or street: 813 S. NATIONAL			
			City, state, zip code: FT. SCOTT, KS. 66701			
4. Locate with "X" in section below:			Sketch map:			
5. Type and color of material			From	To	6. Bore hole dia. 6 3/4 in. Completion date 4/1/78	
TOPSOIL			0'	3'	7. Cable tool <input checked="" type="checkbox"/> Rotar <input type="checkbox"/> Driven <input type="checkbox"/> Dug	
SANDSTONE			3'	7'	<input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
CLAY			7'	10'	8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry	
LIMESTONE			10'	17'	<input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input checked="" type="checkbox"/> Stock	
BLACK SHALE			17'	21'	<input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
LIMESTONE			21'	27'	9. Casing: Material plastic Height: Above or below	
BLACK SHALE			27'	32'	Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface 18 in.	
CLAY w/SAND V-FINE			32'	38'	RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight <input type="checkbox"/> lbs./ft.	
GRAY SHALE w/SAND, BROWN			38'	82'	Dia. 5 in. to 160 ft. depth Wall Thickness: inches or	
LIMESTONE			82'	91'	Dia. 1 1/2 in. to <input type="checkbox"/> ft. depth gauge No. 365	
GRAY SHALE w/SAND FINE			91'	115'	10. Screen: Manufacturer's name Vinylplex	
LIMESTONE, BROKEN w/V-FINE SAND			115'	119'	Type PE-PVC PLASTIC Dia. 5" I.D.	
GRAY SHALE			119'	132'	Slot gauge 1/2" (500) Length 37'	
LIMESTONE			132'	138'	Set between 36' ft. and 80' ft.	
BLACK SHALE + SAND			138'	147'	116' ft. and 118' ft.	
GRAY SHALE (Use a second sheet if needed)			147'	160'	Gravel pack? NO Size range of material	
18. Elevation:			11. Static water level: 20 ft. below land surface Date 8/28/78			
19. Remarks:			12. Pumping level below land surfaces:			
<p>CONCRETE SLAB + Sump TO BE SET</p> <p>18" to 24" BELOW SURFACE, BY CUSTOMER</p> <p>WITH WELL HEAD CAP ADVISED,</p> <p>BELOW GROUND LEVEL PUMP HOUSE</p>			<p>____ ft. after ____ hrs. pumping ____ g.p.m.</p> <p>____ ft. after ____ hrs. pumping ____ g.p.m.</p> <p>Estimated maximum yield 40 gal PER DAY g.p.m.</p>			
Topography:			13. Water sample submitted: ____ mo./day/yr.			
<input checked="" type="checkbox"/> Hill			<input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date			
<input checked="" type="checkbox"/> Slope			14. Well head completion:			
<input type="checkbox"/> Upland			<input type="checkbox"/> Pitless adapter ____ inches above grade			
<input type="checkbox"/> Valley			15. Well grouted? NO Yes NO			
			With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete			
			Depth: From 0 ft. to 10 ft.			
			16. Nearest source of possible contamination:			
			ft. 300 Direction SOUTH Type SEPTIC TANK			
			Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
			17. Pump: Not installed			
			Manufacturer's name MIC DANNFELD			
			Model number ____ HP 1/2 Volts 110			
			Length of drop pipe 120 ft. capacity 18 g.p.m.			
			Type:			
			<input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine			
			<input checked="" type="checkbox"/> Jet <input type="checkbox"/> Reciprocating			
			<input type="checkbox"/> Centrifugal <input type="checkbox"/> Other			
			20. Water well contractor's certification:			
			This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. 380			
			THOMAS L. MORRIS DRILLING			
			Business name License No. 1111 S. MARGRAVE FT. SCOTT			
			Address 1111 S. MARGRAVE FT. SCOTT			
			Signed Thomas L. Morris Date 4/8/79			
			Authorized representative			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5