


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County BUTLER	Fraction SW 1/4 NE 1/4	Section number 6	Township number T 27 SOUTH S	Range number R 6THAM E/W
2. Distance and direction from nearest town or city:	5 MI. NW OF LEON		3. Owner of well: ROBERT E THORBURN		
Street address of well location if in city:	4 MI. N 1 MI. W		R.R. or street: RR 1 BOX 27E		
			City, state, zip code: LEON, KS 66204		
4. Locate with "X" in section below:	Sketch map:		6. Bore hole dia. 8 in. Completion date 9-20-80		
			Well depth 170 ft. 9-20-80		
			7. ☒ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
			8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
			9. Casing: Material ☐ Height: Above or below Threaded ☐ Welded ☒ Surface 18 in. RMP STYRENE Weight ☐ lbs./ft. Dia. 5 in. to 170 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. TYPE 200		
5. Type and color of material	From	To	10. Screen: Manufacturer's name PERATION		
Soil	0	3	Type STYRENE Dia. 5		
yellow clay	3	7	Slot/gauze 1/4 Length 40		
Shale	7	20	Set between 170 ft. and 130 ft.		
limo	20	41	Gravel pack? ☒ Size range of material 1/2		
Red bed	41	48	11. Static water level: 50 ft. below land surface Date 9-75-80		
limo	48	55	12. Pumping level below land surfaces:		
Shale	55	65	☐ ft. after ☐ hrs. pumping ☐ g.p.m.		
limo	65	80	☐ ft. after ☐ hrs. pumping ☐ g.p.m.		
Shale Dark	80	93	Estimated maximum yield 300 g.p.m.		
limed shale	93	119	13. Water sample submitted: ☒ Yes ☐ No Date		
Shale	119	130	14. Well head completion: 18 in.		
limo	130	145	☐ Pitless adapter ☒ 18 in. inches above grade		
Shale	145	148	15. Well grouted? ☒ Yes		
fine sand carry water	148	157	With: ☐ Neat cement ☒ Bentonite ☐ Concrete		
Shale	157	163	Depth: From 0 ft. to 10 ft.		
lime	163	170	16. Nearest source of possible contamination:		
			ft. 300 Direction S.W. Type POND		
			Well disinfected upon completion? ☒ Yes ☐ No		
			17. Pump: ☒ Not installed		
			Manufacturer's name NA		
			Model number ☐ HP ☐ Volts ☐		
			Length of drop pipe 150 ft. capacity ☐ g.p.m.		
			Type:		
			☒ Submersible ☐ Turbine		
			☐ Jet ☐ Reciprocating		
			☐ Centrifugal ☐ Other		
18. Elevation:	19. Remarks:		20. Water well contractor's certification:		
Topography:	Over Kansas rules a regulation		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.		
☐ Hill			Jeffrey Well Drilling		
☐ Slope			Business name Box 346 Eureka KS 65		
☒ Upland			Address Box 346 Eureka KS 65		
☐ Valley			Signed Jeffrey Well Drilling Date 9-20-80		
			Authorized representative Jeffrey Well Drilling Date 9-20-80		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5