


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Butler	Fraction SW 1/4 SE 1/4 NW 1/4	Section number 22	Township number T 27 S	Range number R 6 E/W
2. Distance and direction from nearest town or city: 1 mile next to RR track Street address of well location if in city:				3. Owner of well: City of Leon R.R. or street: City, state, zip code: Leon, Kansas 67074		
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile				Sketch map: 		
5. Type and color of material				From	To	
Soil and clay				0	18	
Gravel (possible water)				18	23	
Shale-green (possible water)				23	25	
Lime-white				25	28	
Shale-blue				28	33	
Lime-blue				33	37	
Shale-blue				37	48	
Shale-gray				48	57	
Redbed (water on top of this)				57	71	
Shale-green & lime				71	79	
Shale-gray				79	85	
Shale-blue				85	100	
(Use a second sheet if needed)						
18. Elevation: Topography: Hill Slope Upland ☒ Valley		19. Remarks: #9 Section will determine the amount of casing		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Abraham, Plummer, & Brown 181A Business name Address: Leon, Kansas 67074 Signed: Jay Abraham Date: 11-9 Authorized representative		
				21. Bore hole dia. 10 1/2 in. Completion date 10-19-80 Well depth 100 ft. 7. ☒ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary 8. Use: ☐ Domestic ☒ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other 9. Casing: Material steel Height: Above or below Threaded ☐ Welded ☐ Surface ☐ in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. 10. Screen: Manufacturer's name Abraham, Plummer, & Brown Type Slots Dia. 16" Slot/gauze 1/2 Length 5 Set between 18 ft. and 25 ft. ft. and ft. Gravel pack? ☒ Size range of material 3/4 11. Static water level: 25 ft. below land surface Date 10-18-80 12. Pumping level below land surfaces: Comp. Draw Dn. ft. after hrs. pumping g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield 1200 gph g.p.m. 13. Water sample submitted: ☒ Yes ☐ No Date 14. Well head completion: Pitless adapter _____ Inches above grade 15. Well grouted? yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 3 ft. to 18 ft. 16. Nearest source of possible contamination: ft. 1500 Direction SW Type Tank battery Well disinfected upon completion? ☒ Yes ☐ No 17. Pump: ☒ Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5