

WELL #3


WATER WELL RECORD Form WWC-5 KSA 82a-1212

LOCATION OF WATER WELL: County: Sedgwick	Fraction SW 1/4 SE 1/4 NE 1/4	Section Number 1	Township Number T 28 S	Range Number R 1 E
--	---	----------------------------	----------------------------------	------------------------------

Distance and direction from nearest town or city street address of well if located within city?

5800 E. Pawnee, Wichita, Kansas

WATER WELL OWNER: Cessna Aircraft Co. RR#, St. Address, Box # : P. O. Box 1521 City, State, ZIP Code : Wichita, KS 67201	Board of Agriculture, Division of Water Resources Application Number:
---	--

LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	DEPTH OF COMPLETED WELL: 36.7 ft. ELEVATION: 1313.55
	Depth(s) Groundwater Encountered 1. 24.6 ft. 2. . ft. 3. . ft.
	WELL'S STATIC WATER LEVEL 24.0 ft. below land surface measured on mo/day/yr 10/16/84
	Pump test data: Well water was n/a ft. after . hours pumping . gpm
	Est. Yield n/a gpm: Well water was . ft. after . hours pumping . gpm
	Bore Hole Diameter 8.0 in. to 37.0 ft., and . in. to . ft.
	WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well
	Was a chemical/bacteriological sample submitted to Department? Yes . No X ; If yes, mo/day/yr sample was submitted
	Water Well Disinfected? Yes X No

TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 2 PVC 4 ABS Blank casing diameter 4.0 in. to 26.1 ft. Dia 4.0 in. to 36.7 ft. Dia . in. to . ft. Casing height above land surface 30.24 in., weight . lbs./ft. Wall thickness or gauge No. 40	5 Wrought iron 8 Concrete tile CASING JOINTS: Glued . Clamped . 6 Asbestos-Cement 9 Other (specify below) Welded . 7 Fiberglass Threaded X
TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 10 Asbestos-cement 11 Other (specify) . 12 None used (open hole)	SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify) .
SCREEN-PERFORATED INTERVALS: From 26.1 ft. to 31.1 ft. From . ft. to . ft. From . ft. to . ft. From . ft. to . ft.	GRAVEL PACK INTERVALS: From 22.0 ft. to 37.0 ft. From . ft. to . ft. From . ft. to . ft. From . ft. to . ft.

GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other . Grout Intervals: From 1.0 ft. to 22.0 ft. From . ft. to . ft. From . ft. to . ft.	What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) Landfill 13 Insecticide storage . How many feet? 50
---	---

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0.0	7.5	Dark Gray, Olive Gray, Olive Brown Silty Clay, Little Sand with Concrete and Ceramic Pieces			
7.5	30.5	Olive Gray with Olive Brown Highly Weathered Shale with Occasional Gypsum			
30.5	37.0	Dark Gray Weathered Shale with Calcareous Material and Gypsum			

CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was 1 constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 10/16/84 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 416 This Water Well Record was completed on (mo/day/yr) 11/3/84
Under the business name of Terracon Consultants, Inc. by (signature) <i>[Signature]</i>

INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.