

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Sedgwick	SW 1/4 NW 1/4 SW 1/4	3	T 28 S	R 1 <u>(E)W</u>

Distance and direction from nearest town or city street address of well if located within city?

2900 S. Hydraulic, Wichita, KS

2 WATER WELL OWNER: Full Service Beverage Co.

RR#, St. Address, Box # : 2900 S. Hydraulic

Board of Agriculture, Division of Water Resources

City, State, ZIP Code : Wichita, KS 67216

Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL: 23 ft. ELEVATION: unknown

Depth(s) Groundwater Encountered 1. 15 ft. 2. ft. 3. ft.

WELL'S STATIC WATER LEVEL 15 ft. below land surface measured on mo/day/yr 12/13/89

Pump test data: Well water was ft. after hours pumping gpm

Est. Yield gpm: Well water was ft. after hours pumping gpm

Bore Hole Diameter 6.5 in. to 23 ft. and in. to ft.

WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well

1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)

2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well

Was a chemical/bacteriological sample submitted to Department? Yes No X; If yes, mo/day/yr sample was submittedWater Well Disinfected? Yes No X

5 TYPE OF BLANK CASING USED:

1 Steel

3 RMP (SR)

5 Wrought iron

8 Concrete tile

CASING JOINTS: Glued Clamped

2 PVC

4 ABS

6 Asbestos-Cement

9 Other (specify below)

Welded

Blank casing diameter 2 in. to 23 ft. Dia in. to ft. Dia in. to ft.

7 Fiberglass

Threaded X

Casing height above land surface 0 in., weight lbs./ft. Wall thickness or gauge No.

TYPE OF SCREEN OR PERFORATION MATERIAL:

1 Steel

3 Stainless steel

5 Fiberglass

X PVC

10 Asbestos-cement

2 Brass

4 Galvanized steel

6 Concrete tile

8 RMP (SR)

11 Other (specify)

12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:

1 Continuous slot

X Mill slot

5 Gauzed wrapped

8 Saw cut

11 None (open hole)

2 Louvered shutter

4 Key punched

6 Wire wrapped

9 Drilled holes

SCREEN-PERFORATED INTERVALS: From 13 ft. to 23 ft. From ft. to ft. From ft. to ft. From ft. to ft.

7 Torch cut

10 Other (specify)

GRAVEL PACK INTERVALS: From 11 ft. to 23 ft. From ft. to ft. From ft. to ft. From ft. to ft.

6 GROUT MATERIAL:

1 Neat cement

2 Cement grout

3 Bentonite

X Other Volclay Grout

Grout Intervals: From 1 ft. to 9 ft. From ft. to ft. From ft. to ft. From ft. to ft.

What is the nearest source of possible contamination:

1 Septic tank

4 Lateral lines

7 Pit privy

10 Livestock pens

14 Abandoned water well

2 Sewer lines

5 Cess pool

8 Sewage lagoon

X1 Fuel storage

15 Oil well/Gas well

3 Watertight sewer lines

6 Seepage pit

9 Feedyard

12 Fertilizer storage

16 Other (specify below)

13 Insecticide storage

Direction from well?

How many feet?

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	6"	Ashpalt			
6"	5.0'	Clay;dark brown; 5-10% Fine sand			
5.0	7.0	Clay;gray; 5-10% fine sand			
7.0	10.5	Clay;brown; mottled; 10-15% fine sand			
10.5	12.0	Silty Sand; gray-brown; fine grained;silt seams			
12.0	15.0	Sand; light yellowish-brown; fine grained; 5% gravels well sorted; moist.			
15.0	16.0	Sand; same as above; gypsum seam			
16.0	20.0	Sand; coarse; poorly sorted light tan-gray; 5-10% gravels; saturated			
20.0	23.0	Sand; same as above; slightly more coarse; 10-15% gravels			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (X) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 12/13/89 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 471

This Water Well Record was completed on (mo/day/yr) 12/13/89

under the business name of HWS Technologies Inc.

by (signature)