

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
County: <u>Sedgwick</u>		<u>SE 1/4 SE 1/4 SE 1/4</u>		<u>4</u>		T <u>28</u> S		R <u>1</u> <u>EW</u>	
Distance and direction from nearest town or city street address of well if located within city? <u>3139 S. Hydraulic, Wichita, KS. 67216</u>									
2 WATER WELL OWNER:		Commercial Rental Property							
RR#, St. Address, Box # :		<u>3139 S. Hydraulic</u>				Board of Agriculture, Division of Water Resources			
City, State, ZIP Code :		<u>Wichita, KS. 67216</u>				Application Number:			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: <u>20'</u> ft. ELEVATION:							
		Depth(s) Groundwater Encountered <u>14'6"</u> ft. 2. ft. 3. ft.							
		WELL'S STATIC WATER LEVEL <u>12.80</u> ft. below land surface measured on mo/day/yr <u>6-3-94</u>							
		Pump test data: Well water was ft. after hours pumping gpm							
		Est. Yield gpm: Well water was ft. after hours pumping gpm							
		Bore Hole Diameter: <u>7 1/2"</u> in. to <u>20'</u> ft., and in. to ft.							
		WELL WATER TO BE USED AS:							
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 11 Injection well 2 Irrigation 4 Industrial 7 Lawn and garden only <u>10</u> Monitoring well 12 Other (Specify below)							
		Was a chemical/bacteriological sample submitted to Department? Yes <u>No</u> X; If yes, mo/day/yr sample was submitted							
		Water Well Disinfected? Yes <u>No</u>							
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued Clamped							
1 Steel 3 RMP (SR)		Welded							
<u>2 PVC</u> 4 ABS		Threaded <u>X</u>							
Blank casing diameter: <u>2.375</u> in. to <u>9'</u> ft. Dia		SDR <u>13</u> ft.							
Casing height above land surface: <u>Flush</u> in., weight lbs./ft. Wall thickness or gauge No. <u>SCH 40</u>									
TYPE OF SCREEN OR PERFORATION MATERIAL:		<u>7 PVC</u>							
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR)		10 Asbestos-cement							
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS		11 Other (specify)							
		12 None used (open hole)							
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)							
1 Continuous slot <u>3 Mill slot</u> 6 Wire wrapped 9 Drilled holes									
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)									
SCREEN-PERFORATED INTERVALS: From <u>19'</u> ft. to <u>9'</u> ft.									
GRAVEL PACK INTERVALS: From <u>19'6"</u> ft. to <u>7'</u> ft.									
6 GROUT MATERIAL:		1 Neat cement <u>2</u> Cement grout <u>3</u> Bentonite 4 Other							
Grout Intervals: From <u>7'</u> ft. to <u>4'</u> ft. From <u>4'</u> ft. to <u>0'</u> ft.									
What is the nearest source of possible contamination:		1 Septic tank 4 Lateral lines 7 Pit privy <u>11</u> Fuel storage <u>Four</u> 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage 16 Other (specify below)							
Direction from well? <u>East North East</u>		How many feet? <u>120'</u>							
FROM	TO	LITHOLOGIC LOG				FROM	TO	PLUGGING INTERVALS	
0	1.75	Med brn loamy silty soil, dry, earthy odor, roots.							
1.75	5	Fine grained tan silty sand, dry, no odor, soft, well sorted & rounded grains.							
5	7.25	Med brn silty clay, firm, no odor.							
7.25	8	Fine grained tan sand, dry, no odor.							
8	10	Dk brn clayey silt, iron oxides, moist, no odor.							
10	20	Fine-coarse grained sand, wet at 14'5 Subrounded, poorly sorted.							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) <u>constructed</u> (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>6-1-94</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>539</u> This Water Well Record was completed on (mo/day/yr) <u>6-9-94</u> under the business name of <u>JB Environmental Drilling</u> by (signature) <u>James Bieber</u>									